

SCHEDULE OF QUANTITY

Name of Work:-A/R & M/O GWSS Sunni in NAC Sunni Tehsil Sunni Distt. Shimla(SH:-C/O Protection wall for Main Storage TaNk)					Estimated Cost Rs. 219680 /-		
					Earnest Money Rs 4500/--		
					Time Limit:- 2 Month		
S.No	Description of items.	Quantity.		Rates.		Unit.	Amount.
				In fig.	In Words.		
1	Demolishing stone rubble masonry manually/by machanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge: In cement mortar).	44.80	Cum			Per Cum	0.00
2	Providing and laying cement concrete 1:5:10 (1 cement : 5sand : 10 graded stone aggregate 40 mm nominal size)with 15% plum and curing complete excluding cost of from work in retaining wall/ breast walls the size of plums shall usually be 150mm to 300 mm as per HPPWD Specification.	29.40	Cum			Per Cum	0.00
3	Providing form work with steel plates 3.15 mm thick welded with angle iron in frames 30x30x5 mm so as to give a fair finish i/c centring ,shuttering, strutting and propping etc. with wooden battens & ballies, ht. of propping & centring below supporting floor to ceiling not exceeding 4 mtrs. & removal of the same for insitu-reinforced concrete work in :						
	i) Vertical surfaces such as walls (any thickness) partitions and the like including attached pilasters , buttresses, plinth and string courses and the like .	28.00	Sqm			Per Square Metre	0.00
5	Providing & Fixing of PVC pipe 100mm dia	15.00	Rmt			Per Rmt	0.00
(Rupees.....)							

TERMS AND CONDITIONS

- 1 Use of vibrator in mendatory for RCC/CC work
- 2 5% payment shall be with held for testing of line & civil structures
- 3 Cement will be issued to the contractors from IPH Store Suni @ Rs 305/- per bag PPC .
- 4 Steel will be issued to the contractors from IPH Store Suni @ Rs 52.00 per/Kg.
- 5 The work will be executed as per PWD/IPH specification and as per the direction of the Engineer-in-Charge.
- 6 The sale tax, Labour cess & Income tax will be deducted from every bill.

Executive Engineer,
Jal Shakti Division,Suni,
Distt. Shimla H.P