

**Schedule of Quantity**

<b>Name of work:- Providing LIS Seund Hathithan Khokhan jamot &amp; Hat in Tehsil Bhunter Distt kullu H.P. (SH:- C/O of G.I Wire &amp; Prov, Laying and Jointing of Hume Pipe NP2 1000mm Dia) Phase-III</b>		<b>Estimated cost</b>		<b>452068.00</b>
		<b>Earnest money</b>		<b>9041.00</b>
		<b>Time</b>		<b>3 months</b>
<b>S.No.</b>	<b>Description of items</b>	<b>Quantity</b>	<b>Rate</b>	<b>Amount</b>
1.00	Excavation in foundation trenches etc. in earth work lift up to 1.5 mtrs. Stacking the excavated soil not more than 3 metres away from the edge of excavation and then returning the stacked soil in 15 cm layers when required in to plinth and sides of foundations, consolidating each deposited layer by ramming , watering and then disposing of all surplus excavated earth as directed with in a lead of 20 metres in pick jumper work.	18.75	cum	
2.00	Wire crates made of G.I.wire filled with boulders with square cut faces against the wire, (Boulder filling to be measured and paid for separately) i/c all leads and lifts. (a) G.I.Wire 5mm thick corresponding to SWG-6(15Cmx15cm.Mesh). As per direction of Engineer-in-charge	1000.00	sqm	
2.00	Wire crate made of G.I wire filled with boulders with square cut faces against the wire (Wire crate to be measured and paid for separately) the weight of each boulder should not lese then 18 kg and as per satisfaction all lifts as per the direction of Engineer-in-Charge.	234.38	cum	

**TERMS AND CONDITIONS :-**

- 1 The contractor shall be responsible for watch and ward of material issued to him and in the event of any theft or loss, the recovery will be made at the double cost of store issue rates.
- 2 The rates should be inclusive of carriage of all material to the site of work in all leads and lifts.
- 3 The weight of boulder should be not less then 18Kg
- 4 Income Tax , Sale tax G.S.T. and labour welfare cess shall be deducted from the bill of the contractor as applicable.
- 5 if any condition of NIT is contacditory to each other then the contractor shall be bring it to the notice of Engineer-in-charge . The decision of the Engineer-in-charge shall final
- 6 Contractors shall have registration in Employees Provident fund Qrganization (EPFO) For EPF No. beafor award work

Executive Engineer,  
IPH Division No. II  
Kullu at Bhunter.

<b>Schedule of Quantity</b>					
<b>Name of work:- Providing LIS Seund Hathithan Khokhan jamot &amp; Hat in Tehsil Bhunter Distt kullu H.P. (SH:- C/O of G.I Wire &amp; Prov, Laying and Jointing of Hume Pipe NP2 1000mm Dia) Phase-III</b>			<b>Estimated cost</b>		<b>265483.00</b>
			<b>Earnest money</b>		<b>5310.00</b>
			<b>Time</b>		<b>3 months</b>
<b>S.No.</b>	<b>Description of items</b>	<b>Quantity</b>		<b>Rate</b>	<b>Amount</b>
1.00	Providing Laying & Jointing of Hume pipe NP2 1000mm dia complete in all respect and as per entire satisfaction of the Engineer-in-charge	50.00	Rmt		
2.00	boulder Filling tightly dry hand packed under floor in all leads and lifts	22.50	cum		
3.00	Hiring of excatvator (JCB) including POL charges any damages to the public as well as private property shall be entire responsibility of contractor. The work shall be executed as per the entire satisfaction of the Engineer in charge	15.00	Hour		
				<b>Total</b>	<b>0.00</b>

**TERMS AND CONDITIONS :-**

- 1 The contractor shall be responsible for watch and ward of material issued to him and in the event of any theft or loss, the recovery will be made at the double cost of store issue rates.
- 2 The rates should be inclusive of carriage of all material to the site of work in all leads and lifts.
- 3 The weight of boulder should be not less then 18Kg
- 4 Income Tax , Sale tax G.S.T. and labour welfare cess shall be deducted from the bill of the contractor as applicable.
- 5 if any condition of NIT is contacditory to each other then the contractor shall be bring it to the notice of Engineer-in-charge . The decision of the Engineer-in-charge shall final
- 6 Contractors shall have registration in Employees Provident fund Qrganization (EPFO) For EPF No. beafor award work

Executive Engineer,  
IPH Division No. II  
Kullu at Bhunter.