

Schedule of Quantity

Name of work:- Comand area development work for LIS Bhatgran Tuniseri in tehsil Bhunter Distt Kullu HP.(SH:- C/O Retaining wall from RD 300 to 318		Estimated cost	170161.00
		Earnest money	3403.00
		Time	3 months
S.No.	Description of items	Quantity	Amount
1.00	Excavation in foundation trenches etc. in earth work lift up to 1.5 mtrs. Stacking the excavated soil not more than 3 metres away from the edge of excavation and then returning the stacked soil in 15 cm layers when required in to plinth and sides of foundations, consolidating each deposited layer by ramming , watering and then disposing of all surplus excavated earth as directed with in a lead of 20 metres in pick jumper work.	31.59 cum	
2.00	Providing and laying cement concrete 1:6:12 (1cement :6 sand :12 graded stone agg.40mm nominal size) and curing complete excluding the cost of form work in in foundation and plinth .	5.59 cum	
3.00	Random Rubble masonry /polygonal rubble un-coursed /brought two coat with hard stone of approved quality in foundation and plinth including leveling up cement concrete 1:6:12(1cement:6sand:12graded stone agg.20mm nominal size) in R/walls/B/Wallsin cemet mortar plinth 1:6 (1cement :6sand) including all leads and lifts and carriage of material at site and to the entire satisfaction of Engineer-in-charge	42.32 cum	
4.00	Boulder filling dry hand packed tightly behind retaining wall with in all leads and lifts and to the entire satisfaction of Engineer-in-charge	3.10 cum	

TERMS AND CONDITIONS :-

- 1 The contractor shall be responsible for watch and ward of material issued to him and in the event of any theft or loss, the recovery will be made at the double cost of store issue rates.
- 2 The rates should be inclusive of carriage of all material to the site of work in all leads and lifts.
- 3 Cement will be issued from sub Divisional store Shamshi @ Rs. 298 /- per bag & steel @4600 per qtl of cost from divisional store Shamshi.
- 4 Income Tax , Sale tax G.S.T. and labour welfare cess shall be deducted from the bill of the contractor as applicable.
- 5 Contractors shall have registration in Employees Provident Fund Organization (EPFO) for EPF No. before award of work
- 6 G.I. pipes will be issued free of cost from Divisional store Shamshi

Executive Engineer,
IPH Division No. II
Kullu at Bhunter.

Schedule of Quantity

Name of work:- Comand area development work for LIS Bhatgran Tuniseri in tehsil Bhunter Distt Kullu HP.(SH:- C/O Retaining wall from RD 365 to 380		Estimated cost		141900.00
		Earnest money		2838.00
		Time		3 months
S.No.	Description of items	Quantity	Rate	Amount
1.00	Excavation in foundation trenches etc. in earth work lift up to 1.5 mtrs. Stacking the excavated soil not more than 3 metres away from the edge of excavation and then returning the stacked soil in 15 cm layers when required in to plinth and sides of foundations, consolidating each deposited layer by ramming , watering and then disposing of all surplus excavated earth as directed with in a lead of 20 metres in pick jumper work.	26.33	cum	
2.00	Providing and laying cement concrete 1:6:12 (1cement :6 sand :12 graded stone agg.40mm nominal size) and curing complete excluding the cost of form work in in foundation and plinth .	4.66	cum	
3.00	Random Rubble masonry /polygonal rubble un-coursed /brought two coat with hard stone of approved quality in foundation and plinth including leveling up cement concrete 1:6:12(1cement:6sand:12graded stone agg.20mm nominal size) in R/walls/B/Wallsin cemet mortar plinth 1:6 (1cement :6sand) including all leads and lifts and carriage of material at site and to the entire satisfaction of Engineer-in-charge	35.26	cum	
4.00	Boulder filling dry hand packed tightly behind retaining wall with in all leads and lifts and to the entire satisfaction of Engineer-in-charge	2.72	cum	

TERMS AND CONDITIONS :-

- 1 The contractor shall be responsible for watch and ward of material issued to him and in the event of any theft or loss, the recovery will be made at the double cost of store issue rates.
- 2 The rates should be inclusive of carriage of all material to the site of work in all leads and lifts.
- 3 Cement will be issued from sub Divisional store Shamshi @ Rs. 263 /- per bag & steel @4600 per qtl of cost from divisional store Shamshi.
- 4 Income Tax , Sale tax G.S.T. and labour welfare cess shall be deducted from the bill of the contractor as applicable.
- 5 Contractors shall have registration in Employees Provident Fund Organization (EPFO) for EPF No. before award of work
- 6 G.I. pipes will be issued free of cost from Divisional store Shamshi

Executive Engineer,
IPH Division No. II
Kullu at Bhunter.

Schedule of Quantity

Name of work:- A/R&M/O WSS Badah in tehsil & distt kullu HP(SH:- L/J of additional pipe line to village Badah from RD 0 to 2550		Estimated cost		207744.00	
		Earnest money		4155.00	
		Time		2 months	
S.No.	Description of items	Quantity	Unit	Rate	Amount
1	Excavation in foundation trenches etc. in all kinds of earth work such as spade work, pick work, jumper work saturated /un saturated soil blasting work and chiseling/wedging out of rocks where blasting work prohibited up to all depth and lifts including pumping and bailing out water where ever required stacking the excavated earth not more than 3mtrs.clear from the edge of excavation and then returning the stacked soil in 15cm.layers when required into the plinth sides of foundation etc. consolidating each deposited layer by ramming and watering and then disposing of all surplus excavated material within all leads and lifts, useful material available from excavation to be properly stacked and handed over free of cost to the department as per direction of the Engineer-in Charge.	788.9	Cum		
2	Laying, jointing and testing in trenches galvanized mild steel screwed and socketed /flanged pipes of following diameter and class, tube fittings in trenches i/c carriage of pipes from Sub-Divisional Store to site of work,(Earth work in trenches to be measured and paid for separately) complete in all respect and to the entire satisfaction of the Engineer-in-charge				
2.1	50 mm dia	2550	RMT		

TERMS AND CONDITIONS :-

- 1 The contractor shall be responsible for watch and ward of material issued to him and in the event of any theft or loss, the recovery will be made at the double cost of store issue rates.
- 2 The rates should be inclusive of carriage of all material to the site of work in all leads and lifts.
- 3 Cement will be issued from sub Divisional store Shamshi @ Rs. 298 /- per bag & steel @4600 per qtl of cost from divisional store Shamshi.
- 4 Income Tax , Sale tax G.S.T. and labour welfare cess shall be deducted from the bill of the contractor as applicable.
- 5 Contractors shall have registration in Employees Provident Fund Organization (EPFO) for EPF No. before award of work
- 6 G.I. pipes will be issued free of cost from Divisional store Shamshi

Executive Engineer,
IPH Division No. II
Kullu at Bhunter.