

SCHEDULE OF QUANTITY

Name of work:-Providing safe drinking water C/O water treatment plant in existing LWSS Dhar Ki Ber G.P.Anji Matla Tehsil Kasauli Distt. Solan (SH:- C/O Brest wall to protect the filter bed).

Estimated Cost Rs:- 113820/-
Earnest Money Rs.:- 2300/-
Time Period:- One month

S.No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation in foundation and trenches etc. in earth work including all kinds of soil such as pick work jumper work,blasting soft and hard rock, conglomerate,upto all leads and lift stacked the excavated soil not more then 3 mtr. Clear from the edge of excavation and then returning the stacked soil in trenches consolidating each deposited layer by ramming and watering and then disposing of all surplus surplus excavated earth as directed by the Engineer-in-Charge	10.80			P/Cum	
2	Providing and laying cement concrete 1:4:8(1cement:4approved sand:8app.graded stone aggregate 40mm nominal size) and curing complete excluding cost of form work in foundation and plinth.including entire carriage of material upto all leads and lifts.	2.70			P/Cum	
3	Providing and laying cement concrete 1:5:10(1cement:5sand:10graded stone aggregate 40mm nominal size)and curing complete excluding cost of form work in foundation and plinth and as per the direction of Engineer in Charge including entire carriage of material upto all leads and lifts.	22.5			P/Cum	
4	Providing form work with steel plates 3.15mm thick and welded with angle iron frame of 30x30x5mm so as to give a fair finish including centring, shuttering and strutting below supporting and propping etc.with wooden battens and ballies height of propping and centring below supporting floor to ceiling not exceeding 4 mtrs and removal of the same for insitu reinforced concrete and plain concrete in:-					
a	vertical surface such as walls(any thickness) partion and the like including attached pillaster,buttresses,plinth and string cources and the like and as per the direction of Engineer in Charge including entire carriage of material upto all leads and lifts.	40.00			P/Sqm.	
					Total Rs:-	

TERMS AND CONDITIONS:-

- 1 The undersigned reserves the right to accept or reject any or all the tenders without assigning any reason thereo
- 2 The work will be got executed as per IPH/PWD specification.
- 3 Security, GST will be deducted as applicable
- 4 Nothing will be paid for sub-standard work/material.
- 5 Work shall be started within 15 days after the date of award and completed in stipulated period.
- 6 Stone aggregate/sand shall be used of approved quarry.

- 7 The quoted rates should include all taxes and carriage charges etc. and nothing extra will be paid on this account
- 8 Useable material found at site while execution will be stacked properly and the same will be the property of the department.
- 9 Cement @ 275/-per bag & steel @ 4700/-per qtl. will be issued from the IPH Store Solan
- 10 Empty bag required to be handed over to the deptt otherwise the recovery @ Rs. 5/-per bag will be made.
- 11 Royalty for the material i.e. Sand, aggregate & stone shall be deducted from the bills as applicable

**Executive Engineer
IPH Division Solan**