

SCHEDULE OF QUANTITY

Name of work :- Remodling of GWSS Chohin Giharwasra In Tehsil Baldwara, Distt. Mandi HP (SH:- C/O RCC Intake Chamber & Laying jointing & testing in trenches for distribution.) UNDER SSCP	Estimated amount :- Rs.	352813.00	/-only
	Earnest Money :- Rs.	7100.00	/-only
	Time : Three months		

Sl. No.	Description of work	No.or Qty.	Unit	RATE		AMOUNT	
				Figures	Words	Rs.	P
1.00	Excavation in foundation, trenches etc. in all kinds of soil such as pick work jumper work, blasting work in soft/hard rock, chiselling in soft/hard rock including wedging out upto all lift, stacking the excavated soil upto all lead clear from the edge o	1199.66	Cum	Per cum.			
2.00	Providing and laying cement concrete 1 : 3 : 6 . (1 cement : 3 sand and : 6 grade stone aggregate 40mm nominal size) and curing complete excluding cost of form work in foundation and plinth upto all leads and lifts as per the direction and to the entire	0.34	cum	Per cum.			
3.00	Providing and laying cement concrete 1 : 1½ : 3 mix. (1 cement : 1½ : sand : 3 graded stone aggregate 20mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in :						
3.01	Walls any thickness but not less than 0.1m thickness including attached pillaster buttresses, plinth and string courses from top of foundation upto two level all floor level as per direction and to the entire satisfaction of Engineer-in-Charge.	0.47	Cum	Per Cum.			
4.00	Cement concrets flooring 1:2:4 (1 cement :2 sand :4 graded stone aggregate 20mm nominal size) laid in one layer finished with a floating coat of neat cement (40 mm thick) as per direction and to the entire satisfacion of Engineer-in-charge upto all lea	0.81	Sqmt	Per Sqmt			
5.00	Providing form work with steel plates 3.15mm thick welded with angle iron in frame 30x30x5mm so as to give a fair finish including centring, shuttering strutting and propping etc. with wooden batten and ballies, in all heights of propping and centring bel						
5.01	In flat surfaces with steel plates such as soffits of suspended floors, roofs, landing and the like floor etc upto all thickness in all leads and lifts as per direction and to the entire satisfaction of Engineer-in-charge.	0.81	Sqmt	Per Sqmt.			
5.02	Vertical surfaces such as wall (any thickness) partitions and the like including attached pillasters, buttresses plinth and string courses and the like in all leads and lifts as per direction and to the entire satisfaction of Engineer-in-charge.	6.30	Sqmt.	Per Sqmt.			
6.00	Providing and laying cement concrete 1:2:4 (1 cement: 2sand: 4graded crushed stone agg. 20mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in :-						
6.01	Suspended floor roofs, landing, shelves and their supports balconies beams, girders, bressumers and cantilevers upto two level all floor level in all leads and lifts as per direction and to the entiresatisfaction of Engineer-in-charge.	0.14	cum.	Per cum.			
7.00	Providing Laying of Tor steel reinforcement for RCC work including bending binding and placing in position including wire upto all floor level as per direction and to the entire satisfaction of Engineer-in-Charge.	42.70	Kg	Per Kg.			
8.00	Laying, jointing and testing in trenches galvanised mild steel tube of light grade screwed and socketed complete including providing and fixing tube fitting such as union, tees, socket etc (excluding cost of bends and valves) for the following dia as per						
	15 mm dia (Light class)	1960.00	Rmt.	Per Rmt			
	20 mm dia (Light class)	320.00	Rmt.	Per Rmt			
	25 mm dia (Light class)	580.00	Rmt.	Per Rmt			
	32 mm dia (Light class)	51.00	Rmt.	Per Rmt			
9.00	Providing and fixing Gun Metal wheel valve of following dia screwed type as per ISI.778-ISI. Marked complete in all respect as per direction and to the entire satisfacioln of Engineer-in-Charge..						
	15 mm dia	2.00	Nos	each			

20 mm dia	2.00	Nos	each		
25 mm dia	2.00	Nos	each		
32 mm dia	3.00	Nos	each		

Total in Figures

Total in Words

TERMS AND CONDITIONS: -

- 1 The work shall be carried out as per HPPWD/IPH specifications and to the entire satisfaction of Engineer -in -Charge.
- 2 Nothing shall be paid for rejected work/material.
- 3 The contractor shall be responsible for watch and ward of material at site of work.
- 4 Cement and steel will be issued to the contractor from IPH Deptt.
Cement :- @ Rs. 268- per bag from IPH Sub-Divnl.Store **Sarkaghat**
Steel shall be issued at Divisional Store Sarkaghat @ Rs. **5083/- per Qtl.** /c Store charges.
- 5 Crushed stone Aggregate shall be used in all concrete work.
- 6 Sand shall be used of approved quarry.
- 7 G.I.Pipe will be issued to the Contractor free of cost from IPH Divisional Store Sarkaghat & G.I. fittings shall be arranged by the contractor at his own cost.
- 8 Sale tax, income tax GST and security etc. as admissible shall be deducted from each runing bill.
- 9 1% labour cess will be deducted from bill of contractor.
- 10 No deviation will be allowed with out prior written approval of Executive Engineer.
5% amount of tendered amount in addition to normal security shall be with held for want of testing which shall be released after successful testing.
- 12 The contractor shall have to obtain EPF/ESIS registration before of commencement of work

Executive Engineer,
I&PH Divn., Sarkaghat.