

SCHEDULE OF QUANTITY							
<b>Name of work:- A/R &amp; M/O GWSS Malgi Bathora ( old) from Darumanin in G.P. Ogli Tehsil Sunni</b>				<b>Estimated Cost:-</b>		<b>114631/--</b>	<b>Only</b>
<b>Sub Head :- C/O RCC Intake chamber 1 No &amp; Laying &amp; jointing of GI Pipe in distribution system )</b>				<b>Earnest Money:-</b>		<b>2300/-</b>	<b>Only</b>
				<b>Time Limit:-</b>		<b>Six</b>	<b>Months.</b>
S.No	Description of items.	Quantity.		Rates.		Unit.	Amount.
				In fig.	In Words.		
1	Excavation in foundation trenches etc.in earth work upto all depths in all kinds of soil such as pick work,jumper work,blasting and chiselling soft/hard rocks where blasting is prohibited in all leads and lifts including trimming and dressing of side levelling of bed to correct grade and returning the stacked soil in trenches in 15cm.layers by ramming and watrering and then disposing of all surplus excavated soil as directed in all leads and lifts and soring strutting/timbering and dewatering where ever required including restoration of un metalled/metalled paved surfaces of its original conditions including caution boards in all respect and to the entire satisfaction of the Engineer-in-Charge.	529.35	Cum			Per Cubic Mere.	
2	Providing and laying cement concrete 1:3:6(1cement:3 sand:6 graded stone agg.20mm nominal size)and curing complete excluding cost of form work in foundation and plinth in all leads and lifts.	0.34	Cum			Per Cubic Metre.	
3	Providing and laying cement concrete 1:1/12:3(M20) (1cement:1 1/2 sand:3 ggraded stone aggregate 20mm nominal size) and curriing complete excluding the cost of form work and reinforcement for reinforced concrete work in:-						
	Walls (any thickness)but not less than 0.1 mtr.thickness)attached pillasters,buttresses,plinth and string courses etc.from top of foundation level upto floor two level in all leads and lifts.	0.47	Cum			Per Cubic metre.	
4	Cement concrete flooring 1:2:4(1cement:2sand:4graded stone agregate 20mm nominal size) laid in one layer finished with a floating coat of neat cement(40mm thick) with all leads and lift.	0.81	Sqm.			Per Square Metre	



## **TERMS AND CONDITIONS**

- 1 Use of vibrator is mandatory for RCC/CC work
- 2 5% payment shall be withheld for testing of line & civil structures
- 3 Cement will be issued to the contractors from IPH Store Suni @ Rs 260/- per bag PPC .
- 4 Steel will be issued to the contractors from IPH Store Suni @ Rs 52.00 per/Kg.
- 5 The work will be executed as per PWD/IPH specification and as per the direction of the Engineer-in-Charge.
- 6 The contractor is fully responsible for watch and ward of material as issued to him
- 7 The sale tax, Labour cess & Income tax will be deducted from every bill.
- 8 Pipe will be issued by the Deptt to the contractor from IPH Store Suni free of cost.
- 9 The pipe fitting such as Tee, Bend , Union etc shall be arranged by the contractor at his own cost.

Executive Engineer,  
I&PH  
Distt Shimla H.P.