

**SCHEDULE OF QUANTITY**

Name of work:- Improvement of LWSS to village Puruwala in Tehsil Paonta Sahib Distt. Sirmour (HP)  
(SH: Providing 428 Nos FHTC to the beneficiaries) Under JJM

Estimated cost Rs 394468/-

Earnest money Rs.7890/-

Time:- Three months.

Sr.No.	Description.	Qty.		Rate.	Unit	Amount.
1	2	3		4	5	6
1	Excavation in drains & channel etc.in earth work in all kinds of soil such as pick work ,jumper work blasting work, decomposed conglomerate saturated soil soft and hard rock including dressing of sides and beds and preparation of sub grade to level or slope including refilling the trenches and disposing of surplus earth upto all leads,lifts disposed earth to be levelled and neatly dressed including jungle clearance and as per directions of the Engineer-incharge	1060.29	Cum.		P/Cum	
2	Laying and jointing of GMS Pipes of various dia in trenches (earth work in trenches to be measured and paid for seperately) including all leads lifts and carriage of material at site as per direction of Engineer-in-charge of following dias.					
	i)15mm dia.	12852	Rmt.		P/Rmt.	
3	Providing and fixing MS clamp of superior quality of the following dia metres complete in all respect and as per direction of the Engineer-in-charge.					
	i) 25mm dia.	50	Nos.		Each.	
	ii) 32mm dia.	68	Nos.		Each.	
	iii)40mm dia.	63	Nos.		Each.	
	iv) 50mm dia.	77	Nos.		Each.	
	v) 65mm dia.	48	Nos.		Each.	
					<b>Total:</b>	

**TERMS AND CONDITIONS:-**

- 1 The work shall be executed as per IPH/PWD specification and instructions of the Engineer-in-charge.
- 2 Security,GST & Income tax shall be deducted as per rules.
- 3 GI Pipe shall be issued free of cost from IPH Store Bhatanwali.
- 4 GI Fitting shall be provided by the contractor.

Executive Engineer,  
I&PH Division,  
Paonta Sahib.

**SCHEDULE OF QUANTITY**

Name of work:- CAD work to LIS Kando Nadi village Naddi in Tehsil Paonta Sahib Distt. Sirmour (HP)  
(SH: Laying & jointing of HDPE Pipe in distribution system ) Part- Ist.

Estimated cost Rs:225689/-

Earnest money Rs.4550/-

Time:- Three Months.

S.No	Sub-Head and item of work.	Qty.		Rates,	Unit	Amount.
1	2	3		4	5	6
1	Excavation in drains & channel etc.in earth work in all kinds of soil such as pick work ,jumper work blasting work, decomposed conglomerate saturated soil soft and hard rock including dressing of sides and beds and preparation of sub grade to level or slope including refilling the trenches and disposing of surplus earth upto all leads,lifts disposed earth to be levelled and neatly dressed including jungle clearance and as per directions of the Engineer-incharge.	661.50	Cum.		P/Cum	
2	Laying & jointing & testing of High Density Polythene pipes for buried water mean and services and for water supply above ground both in side and out side building duty ISI marked IS 4984-1995 as amended upto date in the following grade of material pressere rating and normal dia PN 2.50 grade PE 63 complete in all respect and as per direction of the Engineer in charge. (Earth work to be measured & paid for separately)					
	i) 110mm dia	750	Mtr.		P/Mtr.	
	ii) 125mm dia.	300	Mtr.		P/Mtr.	
3	Providing and fixing of various mm dia polythene high Density PVC HDPE +coupled Equal Tee 125 IS 4984-1995 complete with fitting jointing of HDPE pipes as per IS 7634 Part 1975 latest with upto date ammendments including all leads,lifts and carriage of material at site and as per the directions of the Engineer-in-charge.					
	i) 110mm dia	5	Nos.		Each.	
	ii) 125mm dia.	1	No.		Each.	
4	Providing and fixing of various mm dia polythene high Density PVC HDPE +coupled Equal Bend of of various dia is 4984-1995 complete with fitting jointing of HDPE pipes as per IS 7634 Part 1975 latest with upto date ammendments including all leads,lifts and carriage of material at site and as per the directions of the Engineer-in-charge.					
	i) 110mm dia	5	Nos.		Each.	
	ii) 125mm dia.	1	Nos.		Each.	

5	Providing and fixing of various dia polythene high density PVC HDPE Locking Cap of various dia 4984-1995 complete with fitting jointing of HDPE Pipe as per IS 7634 part 1975 and as per the directions of the Engineer-in-charge.. (Earth work to be measured & paid for separately)					
	i) 110mm dia	5	Nos.		Each.	
	ii) 125mm dia.	1	Nos.		Each.	
					TOTAL:	

### TERMS & CONDITIONS

- 1 The work shall be executed as per IPH/PWD specification and instructions of the Engineer-in-charge.
- 2 Security, Sale tax & Income tax & labour cess shall be deducted as per rules.
- 3 HDPE pipe shall be issued free of cost from IPH store Bhatanwali Paonta Sahib.
- 4 Nothing shall be paid for defective/rejected work.
- 5 The material should be ISI mark.

Executive Engineer,  
I&PH Division,  
Paonta Sahib.

**SCHEDULE OF QUANTITY**

Estimated cost Rs 479942/-  
Earnest money Rs.8400/-  
Time:- Three months.

Name of work:- Aug. & Improvement of Water supply scheme for group of villages of GP Haripurkhol in Tehsil Paonta Sahib Distt. Sirmour (HP) (SH:Providing 331 Nos FHTC to the beneficiaries )Under JJM

Sr.No.	Description.	Qty.		Rate.	Unit	Amount.
1	2	3		4	5	6
1	Excavation in drains & channel etc.in earth work in all kinds of soil such as pick work ,jumper work blasting work, decomposed conglomerate saturated soil soft and hard rock including dressing of sides and beds and preparation of sub grade to level or slope including refilling the trenches and disposing of surplus earth upto all leads,lifts disposed earth to be levelled and neatly dressed including jungle clearance and as per directions of the Engineer-incharge	942.98	Cum.		P/Cum	
2	Laying and jointing of GMS Pipes of various dia in trenches (earth work in trenches to be measured and paid for seperately) including all leads lifts and carriage of material at site as per direction of Engineer-in-charge of following dias.					
	i) 15mm dia.	11430	Rmt.		P/Rmt.	
3	Providing and fixing of peet valve with wheel of superior quality of the following dia metres complete in all respect and as per direction of the engineer-in-charge. 15mm dia	381	Nos.		Each.	
4	Providing and fixing of Tee 25mmx15mm of superior quality of the following dia metres complete in all respect and as per direction of the engineer-in-charge.					
	i) 15mm dia.	381	Nos.		Each.	
5	Providing and fixing of Nipple 15mm dia of superior quality of the following dia metres complete in all respect and as per direction of the engineer-in-charge.	381	Nos.		Each.	
6	Providing and fixing of GI Union of 15mm dia of superior quality of the following dia metres complete in all respect and as per direction of the engineer-in-charge.	381	Nos.		Each.	
7	Providing and fixing of Elbow of 15mm dia of superior quality of the following dia metres complete in all respect and as per direction of the Engineer-in-charge.	762	Nos.		Each.	
8	Providing and fixing of Bib Cock of superior quality complete in all respect and as per direction of the Engineer-in-charge.	381	Nos.		Each.	
	<b>TERMS AND CONDITIONS:-</b>				<b>Total:</b>	

- 1 The work shall be executed as per IPH/PWD specification and instructions of the Engineer-in-charge.
- 2 Security,Sale tax & Income tax shall be deducted as per rules.
- 3 GI Pipe shall be issued free of cost from IPH Store Bhatanwali.
- 4 GI fitting shall be provided by the contractor.

Executive Engineer,  
I&PH Division,  
Paonta Sahib.

## SCHEDULE OF QUANTITY

Name of work:- Re-construction of LWSS Rampur Majri , Ramour Banjaran, Doiyanwala , Ghunglon, Mohrar & Left out Hamlet of village Rampour Bharapur in Tehsil Paonta Sahib Distt. Sirmour (HP) (SH:Providing 341 Nos FHTC to the beneficiaries of Village Rampur Banjran ,Bhanuwala & Mohrar)(Under JJM(Job No.1.

Estimated cost Rs 429555/-  
Earnest money Rs.8600/-  
Time:- Three months.

Sr.No.	Description.	Qty.		Rate.	Unit	Amount.
1	Excavation in drains & channel etc.in earth work in all kinds of soil such as pick work ,jumper work blasting work, decomposed conglomerate saturated soil soft and hard rock including dressing of sides and beds and preparation of sub grade to level or slope including refilling the trenches and disposing of surplus earth upto all leads,lifts disposed earth to be levelled and neatly dressed including jungle clearance and as per directions of the Engineer-in-charge	843.98	Cum.		P/Cum	
2	Laying and jointing of GMS Pipes of various dia in trenches (earth work in trenches to be measured and paid for seperately) including all leads lifts and carriage of material at site as per direction of Engineer-in-charge of following dias.					
	i) 15mm dia.	10230	Rmt.		P/Rmt.	
3	Providing and fixing of peet valve with wheel of superior quality of the following dia metres complete in all respect and as per direction of the engineer-in-charge. 15mm dia	341	Nos.		Each.	
4	Providing and fixing of Tee 25mmx15mm of superior quality of the following dia metres complete in all respect and as per direction of the engineer-in-charge.					
	i) 15mm dia.	341	Nos.		Each.	
5	Providing and fixing of Nipple 15mm dia of superior quality of the following dia metres complete in all respect and as per direction of the engineer-in-charge.	341	Nos.		Each.	
6	Providing and fixing of GI Union of 15mm dia of superior quality of the following dia metres complete in all respect and as per direction of the engineer-in-charge.	341	Nos.		Each.	
7	Providing and fixing of Elbow of 15mm dia of superior quality of the following dia metres complete in all respect and as per direction of the Engineer-in-charge.	682	Nos.		Each.	
8	Providing and fixing of Bib Cock of superior quality complete in all respect and as per direction of the Engineer-in-charge.	341	Nos.		Each.	
<b><u>TERMS AND CONDITIONS:-</u></b>						<b>Total:</b>

- 1 The work shall be executed as per IPH/PWD specification and instructions of the Engineer-in-charge.
- 2 Security,Sale tax & Income tax shall be deducted as per rules.
- 3 GI Pipe shall be issued free of cost from IPH Store Bhatanwali.
- 4 GI fitting shall be provided by the contractor.

Executive Engineer,  
I&PH Division,  
Paonta Sahib

**DRAFT SCHEDULE OF QUANTITY**

Name of work:- Re-construction of LWSS Rampur Majri , Ramour Banjaran, Doiyanwala , Ghunglon ,Mohrar & Left out Hamlet of village Rampour Bharapur in Tehsil Paonta Sahib Distt. Sirmour (HP)(SH:Providing 331 Nos FHTC to the beneficiaries of Village Rampur ,Doiyanwala,Rampur Majri & Gunglon)(Under JJM(Job No.2.

Estimated cost Rs 419559/-  
Earnest money Rs.8400/-  
Time:- Three months.

Sr.No.	Description.	Qty.		Rate.	Unit	Amount.
1	Excavation in drains & channel etc.in earth work in all kinds of soil such as pick work ,jumper work blasting work, decomposed conglomerate saturated soil soft and hard rock including dressing of sides and beds and preparation of sub grade to level or slope including refilling the trenches and disposing of surplus earth upto all leads,lifts disposed earth to be levelled and neatly dressed including jungle clearance and as per directions of the Engineer-incharge	819.00	Cum.		P/Cum	
2	Laying and jointing of GMS Pipes of various dia in trenches (earth work in trenches to be measured and paid for seperately) including all leads lifts and carriage of material at site as per direction of Engineer-in-charge of following dias.					
	i) 15mm dia.	10230	Rmt.		P/Rmt.	
3	Providing and fixing of peet valve with wheel of superior quality of the following dia metres complete in all respect and as per direction of the engineer-in-charge. 15mm dia	331	Nos.		Each.	
4	Providing and fixing of Tee 25mmx15mm of superior quality of the following dia metres complete in all respect and as per direction of the engineer-in-charge.					
	i) 15mm dia.	331	Nos.		Each.	
5	Providing and fixing of Nipple 15mm dia of superior quality of the following dia metres complete in all respect and as per direction of the engineer-in-charge.	331	Nos.		Each.	
6	Providing and fixing of GI Union of 15mm dia of superior quality of the following dia metres complete in all respect and as per direction of the engineer-in-charge.	331	Nos.		Each.	
7	Providing and fixing of Elbow of 15mm dia of superior quality of the following dia metres complete in all respect and as per direction of the Engineer-in-charge.	662	Nos.		Each.	
8	Providing and fixing of Bib Cock of superior quality complete in all respect and as per direction of the Engineer-in-charge.	331	Nos.		Each.	
	<b><u>TERMS AND CONDITIONS:-</u></b>				<b>Total:</b>	

- 1 The work shall be executed as per IPH/PWD specification and instructions of the Engineer-in-charge.
- 2 Security,Sale tax & Income tax shall be deducted as per rules.
- 3 GI Pipe shall be issued free of cost from IPH Store Bhatanwali.
- 4 GI fitting shall be provided by the contractor.

Executive Engineer,  
I&PH Division,  
Paonta Sahib.