

**Schedule of qty**

Estimated cost Rs. 3,82,900/-

Earnest money Rs.7660/-

Time:- Three months.

Name of work:- Providing LWSS Chhari Khad to Tandi and adjoining villages Tehsil Thunag Distt. Mandi (HP)(SH:- Providing and laying C.C. interlocking paver blocks) Job No.I

Sr. No.	Description	Qty.	Rate	Unit	Amount.
1	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibrocompacted upto M-50 grade-C border or kerb block grey or coloured over sub base of concrete with 25mm thick average thickness of cement mortar 1:4 (1 cement :4 sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks/cutting rubbing and polishing complete (Sub base concrete floor to be paid for separately) complete in all respect in all leads and lifts.				
	(i) 60mm thick preinterlocking block	350.00 sqm		Per sqm	
	<b><u>Terms and conditions.</u></b>			<b>Total</b>	

(i) The work shall be executed as per ISI specification and to the entire satisfaction of the Engineer-in-charge.

(ii) The contractor shall be fully responsible for watch and ward of the material at site of work.

(iii) Security, Income Tax, Labour Cess will be deducted from each bill of the contractor as per latest Govt. instructions.

(vi) GST as applicable shall be paid separately as per latest notification of Govt.

(v) Nothing shall be paid for rejected/defected work.

Executive Engineer  
I&PH Division  
Thunag