

**Job No.1**

Estimated Cost Rs:- 2,66,275/-  
 Earnest Money Rs:- 5300/-  
 Time Period:- One month.

**SCHEDULE OF QUANTITY**

**Name of work:-** Providing LWSS to NC/ PC habitation under GP Sirinagar, Bisha, Kawarag and Mahi Tehsil  
 Kandaghat Distt. Solan HP. (SH:- Providing house tap connection to left out families). (Under Jal Jeevan Mission).

Sr. No.	Description	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Excavation in drains and channel etc in earth work in all kinds of soil such as kankar, moorum shingles conglomerate saturated soil and decomposed soft and hard rock hard rock including dressing of sides and beds, disposing of excavated earth with all leads, lifts disposed earth to be levelled and neatly dressed and then returning the stacked soil into foundation and trenches etc. including ramming and consolidating the same wherever required with all leads, lifts and including jungle clearance and as per the direction of Engineer-in-charge.	379.2			P/Cum	
2	Laying, jointing, testing and commissioning in trenches galvanised mild steel tube of following dia (light grade) including providing and fixing tube fittings such as reducer increasers, sockets, union, tees, bends etc. where ever required (earth work in trenches to be measured and paid for separately) and as per the direction of Engineer-in-charge including entire carriage of material upto all leads and lifts.					
	15mm dia	2400			P/Rmt	
	20mm dia	300			P/Rmt	
	25mm dia	80			P/Rmt	
3	Providing & fixing brass tap complete in all respect including entire carriage of material upto all leads & lifts as per direction of the Engineer-in-charge.	48			Each	
4	Providing & fixing tee, elbow, union, sockets, ferrule complete in all respect as per direction of the Engineer-in-charge.	48			Each	
5	Providing & fixing gun metal full way valve of 15mm dia with MS chamber complete in all respect including entire carriage of material upto all leads & lifts as per direction of the Engineer-in-charge.	48			Each	
					<b>Total Rs.:-</b>	

**TERMS AND CONDITIONS:-**

- The undersigned reserves the right to accept or reject any or all the tenders without assigning any reason thereof.
- The work will be got executed as per IPH/PWD specification.
- GST security will be deducted from the contractor bill as applicable.
- Nothing will be paid for sub-standard work/material.
- Work shall be started within 15 days after the date of award and completed in stipulated period.
- Contractor shall be responsible for all leakage in the jointing of pipes, which shall be set right by the contractor at his own cost
- The Contractor is responsible to watch & ward the material at site of work.
- The material/ repair will be guaranteed for a period of one year.
- G.I. pipes will be issued to the contractor free of cost on proper indent at IPH Store Solan. Further carriage and watch and ward will be the responsibility of the contractor. Shortage of G.I. pipe will be recovered on double rate as per Store

**Executive Engineer**  
**I&PH Division Solan**

**Job No-2**

Estimated Cost Rs:- 1,89,657/-

Earnest Money Rs:- 3400/-

Time Period:- One month.

**SCHEDULE OF QUANTITY**

**Name of work:-** Providing LWSS to NC/ PC habitation under GP Tundal & Basha Tehsil Kandaghat Distt. Solan HP.  
(SH:- Providing house tap connection to left out families). (Under Jal Jeevan Mission).

Sr. No.	Description	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Excavation in drains and channel etc in earth work in all kinds of soil such as kankar, moorum shingles conglomerate saturated soil and decomposed soft and hard rock hard rock including dressing of sides and beds, disposing of excavated earth with all leads, lifts disposed earth to be levelled and neatly dressed and then returning the stacked soil into foundation and trenches etc. including ramming and consolidating the same wherever required with all leads, lifts and including jungle clearance and as per the direction of Engineer-in-charge.	271.2			P/Cum	
2	Laying, jointing, testing and commissioning in trenches galvanised mild steel tube of following dia (light grade) including providing and fixing tube fittings such as reducer increasers, sockets, union, tees, bends etc. where ever required (earth work in trenches to be measured and paid for separately) and as per the direction of Engineer-in-charge including entire carriage of material upto all leads and lifts.					
	15mm dia	1700			P/Rmt	
	20mm dia	120			P/Rmt	
	25mm dia	160			P/Rmt	
3	Providing & fixing brass tap complete in all respect including entire carriage of material upto all leads & lifts as per direction of the Engineer-in-charge.	34			Each	
4	Providing & fixing tee, elbow, union, sockets, ferrule complete in all respect as per direction of the Engineer-in-charge.	34			Each	
5	Providing & fixing gun metal full way valve of 15mm dia with MS chamber complete in all respect including entire carriage of material upto all leads & lifts as per direction of the Engineer-in-charge.	34			Each	
					<b>Total Rs.:-</b>	

**TERMS AND CONDITIONS:-**

- The undersigned reserves the right to accept or reject any or all the tenders without assigning any reason thereof.
- The work will be got executed as per IPH/PWD specification.
- GST security will be deducted from the contractor bill as applicable.
- Nothing will be paid for sub-standard work/material.
- Work shall be started within 15 days after the date of award and completed in stipulated period.
- Contractor shall be responsible for all leakage in the jointing of pipes, which shall be set right by the contractor at his own cost
- The Contractor is responsible to watch & ward the material at site of work.
- The material/ repair will be guaranteed for a period of one year.
- G.I. pipes will be issued to the contractor free of cost on proper indent at IPH Store Solan. Further carriage and watch and ward will be the responsibility of the contractor. Shortage of G.I. pipe will be recovered on double rate as per Store

**Executive Engineer**  
**I&PH Division Solan**

**Job No-3**

Estimated Cost Rs:- 2,04,691/-

Earnest Money Rs:- 4100/-

Time Period:- One month.

**SCHEDULE OF QUANTITY****Name of work:-** Providing WSS to PC habitation Rajpuri and Samral in GP Jabli Tehsil Kasauli Distt. Solan HP. (SH:- Providing house tap connection to left out families). (Under Jal Jeevan Mission).

Sr. No.	Description	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Excavation in drains and channel etc in earth work in all kinds of soil such as kankar, moorum shingles conglomerate saturated soil and decomposed soft and hard rock hard rock including including dressing of sides and beds, disposing of excavated earth with all leads, lifts disposed earth to be levelled and neatly dressed and then returning the stacked soil into foundation and trenches etc. including ramming and consolidating the same wherever required with all leads, lifts and including jungle clearance and as per the direction of Engineer-in-charge.	416.25			P/Cum	
2	Laying, jointing, testing and commissioning in trenches galvanised mild steel tube of following dia (light grade) including providing and fixing tube fittings such as reducer increasers, sockets, union, tees, bends etc. where ever required (earth work in trenches to be measured and paid for separately) and as per the direction of Engineer-in-charge including entire carriage of material upto all leads and lifts.					
	15mm dia	1250			P/Rmt	
	20mm dia	300			P/Rmt	
	25mm dia	300			P/Rmt	
3	Providing & fixing brass tap complete in all respect including entire carriage of material upto all leads & lifts as per direction of the Engineer-in-charge.	25			Each	
4	Providing & fixing tee, elbow, union, sockets, ferrule complete in all respect as per direction of the Engineer-in-charge.	25			Each	
5	Providing & fixing gun metal full way valve of 15mm dia with MS chamber complete in all respect including entire carriage of material upto all leads & lifts as per direction of the Engineer-in-charge.	25			Each	
					<b>Total Rs.:-</b>	

**TERMS AND CONDITIONS:-**

- The undersigned reserves the right to accept or reject any or all the tenders without assigning any reason thereof.
- The work will be got executed as per IPH/PWD specification.
- GST security will be deducted from the contractor bill as applicable.
- Nothing will be paid for sub-standard work/material.
- Work shall be started within 15 days after the date of award and completed in stipulated period.
- Contractor shall be responsible for all leakage in the jointing of pipes, which shall be set right by the contractor at his own cost.
- The Contractor is responsible to watch & ward the material at site of work.
- The material/ repair will be guaranteed for a period of one year.
- G.I. pipes will be issued to the contractor free of cost on proper indent at IPH Store Solan. Further carriage and watch and ward will be the responsibility of the contractor. Shortage of G.I. pipe will be recovered on double rate as per Store

**Executive Engineer**  
**I&PH Division Solan**

**Job No.4**

Estimated Cost Rs:- 1,91,625/-

Earnest Money Rs:- 3850/-

Time Period:- One year.

**SCHEDULE OF QUANTITY****Name of work:-** A/R & M/O drinking water supply scheme to Solan Town from Giri River. (SH:- Rewinding of 85 HP motor at raw water stage, repair of pump etc). (Set No.2).

Sr. No.	Description	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Rewinding of raw water motor with F class copper 85 HP including placement of rotor and rotor should be pressed in the stuffer body through computerized machine at Chandigarh complete in all respect including entire carriage of material upto all leads & lifts.	1			Job	
2	Providing & fixing of mechanical seal for KRTE 150- 401 pump complete in all respect including entire carriage of material upto all leads & lifts.	2			P/Set	
3	Providing & fixing ball bearing No. NU 6311 SKF made complete in all respect including entire carriage of material upto all leads & lifts.	1			Each	
4	Providing & fixing ball bearing No. NU 211 C3 SKF made complete in all respect including entire carriage of material upto all leads & lifts.	1			Each	
5	Providing & fixing oil seal complete in all respect including entire carriage of material upto all leads & lifts.	2			Each	
6	Dismantelling and carriage upto work shop and re- installation with testing etc. complete in all respect.	1			Job	
7	Repair of impeller stainless steel for KRTE pump 150-401 including filling of material and marking as per size of impeller complete in all respect.	1			Each	
8	Providing & fixing diffuser for 62 KW KRTE pump complete in all respect including entire carriage of material upto all leads & lifts.	1			Each	
					<b>Total Rs.:-</b>	

**TERMS AND CONDITIONS:-**

- 1 The undersigned reserves the right to accept or reject any or all the tenders without assigning any reason thereof.
- 2 The work should be done as per IPH specification and direction of Engineer-in-Charge.
- 3 Security, GST and other statutory deductions will be made as applicable.
- 4 Work shall be started within 15 days after the date of award and completed in stipulated period.
- 5 Gurantee period for 12 months .

Executive Engineer  
IPH Division Solan