

SCHEDULE OF QUANTITY

Name Of Work:- Improvement of LWSS to Village Puruwala in Tehsil Paonta Sahib, District Sirmour (HP) (SH: - Drilling, Lowering, Assembling & Development of Tube well 60 mtr. Deep). Under JJM

Estimated Cost :-Rs. 318481/-
Earnest Money :-Rs.6400/-
Time:- Three months.

S. No.	Items of Work	Qty.	Rate	Unit	Amount
1	Transportation of suitable truck mounted DTH & OXEX/Percussion Calyx/RC drilling rigs along with necessary accessories etc. to the site of work and erection of rig including leveling etc. complete in all respect and as per the direction of the Engineer-in-Charge.	1		Each	
2	Drilling bores of 200mm dia as per IS-2900-1979 using ODEX (TUBEX) attachment required drilling in collapsible strata conglomerate, boulder pebble, gravels, silt, clay etc. including cost of attachments, consumable stores, bits, water POL etc. complete with system of simultaneous.	60		P/Rmt.	
3	Sppling and lowering of IS marked 175 mm N.B. 5mm thick fin cut MSERW casing pipes as per IS-4270-2001 and requirement of ODEX attachment from approved manufacures complete in all respect and as directions of the Engieer-in-Charge.	60.3		P/Rmt.	
4	Providing and fixing suitable casing shoe and bit tube as per requirement of ODEX attachment complete in all respects and as per direction of the Engineer-in-Charge.	1		Each	
5	Collection and preservaion of soil samples in polythene bags complete in all respect and as per direction of the Engineer-in-Charge.	1		Each	
6	Development of bore well and yield testing with air compressor through V-Notch and disinfection etc. complete in all respects and as per direction of the	10		P/Hrs.	

Total Rs. _____

TERMS AND CONDITIONS

- 1 The work shall be executed as per IPH/PWD specifications and instructions of the Engineer-in-Charge
- 2 Security, GST, Income Tax & Labour cess shall be deducted as per rules.
- 3 No payment shall be made for defective/rejected work/ material.

Executive Engineer,
I & P.H. Division,
Paonjta Sahib.