

**SCHEDULE OF QUANTITY**

<b>Name of Work:-Stock storage(SH:- C/O Septic tank at Jal Shakti Division office building Suni</b>					<b>Estimated Cost Rs. 123110 /-</b>		
					<b>Earnest Money Rs 2500/--</b>		
					<b>Time Limit:- 1 Month</b>		
S.N	Description of items.	Quantity.		Rates.		Unit.	Amount.
				In fig.	In Words.		
1	Excavation in foundations trenches etc. in earth work lift up to 1.50 mtrs stacking the excavated soil not more than 3 mtr clear from the as of excavation and than returing the excavated soil in 15 cm layers when required in to plinths sides of foundations etc. consolidating each deposited layer by ramming and watering and then disposing of all surplus excavated soil as directed within a lead of 20 mtrs P.J.Work:-	27.67	Cum			Per Cum	
2	Disposal including loading unloading and stacking of syrplus excavated soil/material with in a lead of 1 km by M.T. & 200 mtrs Head load at the disposal site	27.67	Cum			Per Cum	
3	Providing and laying cement concrete 1:4:8(1cement:4 sand;8 graded stone crused stone aggregate and 40mm nominal size) and curing complete excluding the cost of from work in teatining wall& Breast wall anchor Block as per HPPWD Specification	3.03	Cum			Per Cum	
4	Providing and laying cement concrete 1:3:6(1cement:3 sand;6 graded stone crused stone aggregate and 40mm nominal size) and curing complete excluding the cost of from work in teatining wall& Breast wall anchor Block as per HPPWD Specification	7.8488	Cum			Per Cum	
5	Providing and laying cement concrete 1:2:4 work(1 cement: 2sand:4 graded stone aggregate 40mm nominal size) and curring complete excluding cost of from work and reinforced concrete work in:-						
	Suspended floors roofs,landings and shelves and their supports,balconies beams girders,bressumers and cantilever up to floor two levels	1.75	Cum			Per Cum	
6	Providing form work with steel plates 3.15mm thick welded with angle iron in frame 30x30x5mm so as to give a fair finish including centring, shuttering ,strutting and propping etc. with wooden battens and ballies height of propping and centring below supporting floor to ceiling in all heights and removal of the same for insitu reinforced concrete and plain concrete workin:-						
	Vertical surfaces such as walls(any thickness)partitons and the like including attached pillasters,buttresses plinth and string courses and the like in all leads and lifts	35.88	Sqm			Per Square Metre	
	Flat surface such as soffits and suspended floors,roofs,landing and the like in all leads and lifts	11.66	Sqm			Per Square Metre	
7	Providing mild stel/ tor steel reinforcement for RCC work including bending,binding and placing in position complete up to floor two level	157.50	Kg			Per Kg	
8	Providing & fixing of C.I. mainhole cover complete in all respect	2.00	No			Each	
<b>(Rupees</b>							

**TERMS AND CONDITIONS**

- 1 Use of vibrator is mandatory for RCC/CC work
- 2 5% payment shall be withheld for testing of line & civil structures
- 3 Cement will be issued to the contractors from IPH Store Suni @ Rs 300- per bag PPC .
- 4 Steel will be issued to the contractors from IPH Store Suni @ Rs 52.00 per/Kg.
- 5 The work will be executed as per PWD/IPH specification and as per the direction of the Engineer-in-Charge.
- 6 The sale tax, Labour cess & Income tax will be deducted from every bill.

Executive Engineer,  
Jal Shakti Division, Suni, .