

SCHEDULE OF QUANTITY

Name of work:- Stcok Storage (SH- Construction of Additional Accommodation for Divisional Office Building at Rabon Solan HP. P/L of roof truss and CGI Roofing).

Estimated Cost:- 901022/-
Earnest Money:- 19000/-
Time Period:- 6 Months

Sr. No.	Description of item.	Qty.	Unit	Rate	Amount.
1	Steel work welded in built up sections, trusses and framed work, including curring, hoisting, fixing in position and applying a priming coat of red led paint. In beams joists channels, angles, tees, flats with connection plates or angle cleets as in main and cross beems, him and jack rafters, purline connected to common rafters and the like. i) In trusses and trussed purlins in buildings).	137.60	Qtl		
2	Providing 0.63 mm thick coloured sheet corrugated G.I. sheet roofing fixed with galvanized iron J or L hooks bolts and nuts 8mm diameter with bitumen and G.I. limpet washers filled with white lead complete excluding the cost of purlins rafters and trusses, as per the direction of Engineer-in-Charge and as per HP.PWD Specification, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts including all incidental charges.	805.10	Sqm		
3	Providing and fixing ridges or hips 60 (sixty) centimeters overall with 0.63 (Zero point Six three) thick G.I. Sheet with galvanized iron J or L hooks, bolts and nuts 8mm dia G.I. Limpet and bitumen washers complete as per the direction of Engineer-in-Charge and as per HP.PWD specification, including carriage of all labour equipment and material to various location through all modes of transportatyion in all leads and lifts, including all incidental charges.	44.00	Rmt		
4	Providing valleys 90 (Ninety) centimeters over all in plain GI sheets 0.63 (Zero point Six three) milimeters thick sheet fixed with galvanized iron J or L hooks, bolts and nuts 8mm dia G.I. limpet Specification, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	48.00	Rmt		

5	Providing and fixing 15 (fifteen) centimeters wide 45 (forty five) centimeters overall semicircular plain GI Sheet gutter with iron brackets 40*3 (forty into three) size bolts and nuts and washers etc. including making necessary connections with rain water pipe complete as per design as per the direction of Engineer-in-Charge and as per HP.PWD specification, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	88.00	Rmt		
6	Providing and fixing MS BP sheet 2 (two) millimeters thick in eaves board/facia/soffits/ceiling including cutting fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-Charge (Base members of steel work shall be measured paid in relevant item of steel, complete as per HP. PWD specification, including carriage of all labour equipment and material to various location through all modes of transportation in all leads lifts and all incidental charges.	42.80	Sqm		
			Total:-		

TERMS AND CONDITIONS:-

- 1 The undersigned reserves the right to accept or reject any or all the tenders without assigning any reason thereof.
- 2 The work will be got executed as per IPH HPPWD specification.
- 3 GST, Security will be deducted from the contractor's bill as applicable.
- 4 All material shall be used as per ISI specifications.
- 5 The quoted rates should include all taxes and carriage charges etc. and nothing extra will be paid on this account.
- 6 Work shall be started within 15 days after the date of award and completed in stipulated period.
- 7 Nothing will be paid for sub-standard work/material.
- 8 The contractor is responsible to watch and guard the material at site of work

**Executive Engineer,
IPH Division Solan.**