

SCHEDULE OF QUANTITY

156 Name of work: Upgradation of Sewerage Treatment Plant 5.15 MLD at Chellian in Tehsil Dharamshala Distt. Kangra (H.P)
(SH: Efficiency enhancement of Sludge drying bed No.4 at STP Chellian)

Estimated Cost Rs: 626297/-
Earnest Money Rs: 12530/-
Time Limit: 3 Months

| Sr No. | Description of items. | Qty. | Unit | Rate | | Amount |
|--------|--|---------|------|------------|----------|--------|
| | | | | in figures | in words | |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| 1 | Providing form work with steel plates 3.15 mm thick welded with angle iron in frame 30x30x5mm so as to give a fair finish including centring, shuttering, strutting and propping etc with batten & ballies, height of propping and centring below supporting floor to ceiling not exceeding 4 mtrs and removal of the same for in-situ-reinforced concrete and plain concrete in: Vertical surface such as wall (any thickness) partition and the like i/c attached pillasters, buttresses plinth and string course including all leads and lifts. | 45.72 | Sqm | | | |
| 2 | Providing and laying cement concrete work 1:2:4(1cement:2sand:4graded stone aggregate 20mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work: In suspended floor roofs,landings, shelves and their supports balconies, beams girders bressumers and centilevers upto floor two level i/c carriage of material within all leads and lifts. | 10.287 | Cum | | | |
| 3 | Providing mild steel/tor steel reinforcement for RCC work including bending, binding and placing in position complete upto floor two level (tor steel) complete with in all leads and lifts. | 257.00 | Kg | | | |
| 4 | Providing and laying S.W. pipe 150mm dia complete in all respect with in all leads and lifts. | 106-00 | Mtr | | | |
| 5 | Removal of sludge and taking out media/silt by excluding in all respect as per direction of Engineer-in-Charge with in all leads and lifts. | 220.480 | Cum | | | |
| 6 | P/L cement concrete 1:5:10(1:cement :5 sand:10 graded stone aggregate 40mm nominal size) with 15% plum and curing complete excluding cost of form work in R/wall / B/wall the size of plum shall usely be be 150mm to 300mm as per PWD specification complete in all respect i/c all leads & lifts. | 22.048 | Cum | | | |
| 7 | P/L cement concrete 1:2:4(1:cement :2 sand:4 graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work in foundation and plinth i/c carriage of material within all leads and lifts. | 22.048 | Cum | | | |
| 8 | P/L Filter Media (Bajri screened, clean, washed and graded stone aggregate 20 mm to 25mm from approved source complete in all respect within all leads and lifts. | 220.48 | Cum | | | |

TERMS AND CONDITIONS:

- 1.The work shall be carried out as per IPH specifications.
- 2.Sales tax & other statutory taxes/levies shall be deducted from all sums payable to the contractor as per Govt. notifications issued from time to time.
- 3.Nothing shall be paid for rejected work/materials.
- 4.Any loss or theft of Govt. material will be responsibility of contractor.
- 5.Cement will be issued to contractor from Divisional Store at Bhuter @ Rs. 311/- per bag.
- 6.Steel will be issued to the contractor from Divisional Store at Bhuter @ Rs. 3950/- per Qtl.
- 7.The final payment will be made after satisfaction of the Engineer-in-charge.

Executive Engineer,
IPH Division,
Dharamshala