

SCHEDULE OF QUANTITY

Name of work: Providing LWSS to NC/PC habitation of CV Tatiana GP Tatiana in Tehsil Paonta Sahib Distt.Sirmour (HP)
(SH: Laying & jointing of GI Pipes)

Estimated cost Rs. 282842/-
Earnest money Rs5700/-
Time:- Three Months

S.No	Sub-Head and item of work.	Qty.		Rate.	Unit	Amount.
1	2	3		4	5	6
1	Excavation in drains & channel etc.in earth work in all kinds of soil such as pick work ,jumper work blasting work, decomposed conglomerate saturated soil soft and hard rock including dressing of sides and beds and preparation of sub grade to level or slope including refilling the trenches and disposing of surplus earth upto all leads,lifts disposed earth to be levelled and neatly dressed including jungle clearance and as per directions of the Engineer-in-charge	1660.05	Cum.		P/Cum.	
2	Laying & jointing of GMS pipes of following dia & class including all leads,lifts and carriage of material and earth work etc. complete in all respect complete in all respect and as per direction of the Engineer-in-charge.					
	I) 15mm dia (L)	4360.00	Rmt.		P/Rmt.	
	ii) 25mm dia (L)	3340.00	Rmt.		P/Rmt.	
	iii) 32mm dia (L)	2180.00	Rmt.		P/Rmt.	
	iv) 40mm dia.(L)	660.00	Rmt.		P/Rmt.	
3	Fixing of Peet valve of Gun Metal of superior quality of following dias complete in all respect and as per direction of the Engineer-in-charge.					
	I) 15mm dia (L)	15.00	Nos		Each	
	ii) 25mm dia (L)	10.00	Nos		Each	
	iii) 32mm dia (L)	10.00	No.		Each	
	iv) 40mm dia.(L)	10.00	No.		Each	
TERMS & CONDITIONS						Total:

- 1 The work shall be executed as per IPH/PWD specification and instructions of the Engineer-in-charge.
- 2 Security,Sale tax & Income tax shall be deducted as per rules.
- 3 GI Pipe & Fitting shall be issued free of cost from IPH Store Bhatanwali Paonta Sahib.
- 4 In addition to normal security 5% will be withheld for want of testing and released after successful testing.

Executive Engineer,
I&PH Division,
Paonta Sahib.