

Schedule of quantity.		Estimated Cost : 852855			
Name of work: Providing LWSS Dodni age .Bhatgran in Tehsil Bhuntar Distt. Kullu HP (SH:- C/O storage tank at pt H 10000 ltrs and at pt. F 21500 ltr capacity , Laying jointing of G.I Pipe at pt. B-H,B-F,H-H2,C-D,E-E1,E-E2,E-E3)		Earnest Money : 17057			
		Time limit: 6 Month			
S.No.	Description of itmes	Qty.	Unit	Rate	Amount.
1	Excavation in foundation trenches etc. in all kinds of soil such as pick work,jumper work,blasting hard or soft rock,by chieselling where the blasting work is water with in all heights stacking the excavated soil with in all leads clear from the edge of excavation and then returning the stacked soil in 15 cms. layers when required in to plinths, sides of foundations consolidating each deposited layer by ramming and watering and then disposing of all surplus excavated earth as per the direction of Engineer-in-charge with in all leads and lifts complete in all respect.	3214.32	Cum		
2	Providing form work with steel plates 3.15 mm thick welded with angle iron in frame 30x30x5 mm so as to give a fair finish including centering,shuttering,strutting and propping etc. with wooden battons and ballies,height of propping and centering below supporting floor to ceiling not exceeding 4.00 mtr and removal of the samefor in situreinforced and plain concrete work in :-				
3	Flat surfaces such as soffits of suspended floors,roofs,landing and the like floor etc. up to 20 mm in thickness including all leads and lifts complete in all respect.	13.35	Sqm		
3.1	Vertical surface such as walls(any thickness) partitions and the like including attached pillasters, butteresses, plinth and string courses and the like.	96.52	Sqm		
4	Providing tor steel reinforcement for RCC work including bending binding and placing in position with in all leads and lifts complete in all respect.	860.00	Kg.		
5	Providing and laying cement concrete 1:4:8(1cement:4 sand: 8 graded stone aggregate 40 mm nominal size) and curing complete excluding the cost of form work in foundation and plinth.	4.55	Cum		
6	Providing and laying cement concrete 1:11/2 :3 (1cement: 1 1/2 sand: 3graded stone aggregate 20 mm nominal size)and curing complete excluding the cost of form work and reinforcement in:-				
	i) Foundation and plinth.	3.61	Cum		
	ii) Walls(any thickness but ot less than 0.1 mtr thickness) attached pilasters, buttresses, plinth and string courses etc. from top of foundation level up to floor two level.	7.09	cum		

S.No.	Description of itmes	Qty.	Unit	Rate	Amount.
	iii) suspended floors, roofs,landings and shelves and their supports, balconies, beams, girders, bressumers and cantilivers up to floor two level.	1.58	Cum		
7		2.00	Each		
8	Laying , jointing and testing in trenches galvanised mild steel of following dia metre, including carriage of pipe and cost of fitting such as bends, tees, air valve, unions and collars etc, as per direction and to the entire satisfaction of Engineer in charge. (Earth work to be measured and paid for seperately)				
	15 mm	2350.00	Rmt		
	20 mm	1200.00	Rmt		
	25 mm	1500.00	Rmt		
	32 mm	3125.00	Rmt		

Total =

Note: Term and conditions

- 1 The contractor shall be responsible for watch and ward of material issued to him and in the event of any theft or loss, the recovery will be made at the double cost of store issue rates.
- 2 The rates should be inclusive of carriage of all material to the site of work in all leads and lifts.
- 3 The rates should be inclusive of all prevalent taxes of Center or State .
- 4 Cement will be issued from sub Divisional store Shamshi @ Rs. 263 /- per bag & steel will be issued @4600/- Qtl. from divisional store Shamshi.
- 5 The Work should be executed as per HP.PWD specifications, as per recommendations of CPHEEO Manual on water supply and as per relevant IS Code and specifications.
- 6 1% (One percent) Labour cess (Non refundable) will be deducted on gross amount from each bill besides other deductions such as income Tax, Surcharge on Income Tax and Sales Tax etc.
- 7 Contractors shall have registration in Employees Provident Fund Organization (EPFO) for EPF No. before award of work
- 8 G.I. pipes will be issued free of cost from Divisional store Shamshi

**Executive Engineer
IPH Division kullu-II at Bhuntar.**