

Schedule of quantity.

Estimated Cost 396351

Name of work:- PWSS Banjar in Tehsil Bhuntar Distt. Kullu HP. (SH:- C/O Plum concrete wall & wire crated embankment)

Earnest Money 7927

Time:- 6 Month

S.No.	Description of items.	Rate	Unit	Amount
1	Excavation in foundation trenches etc in earth work in all kind of soil containing spade work, blasting work, jumper work including decomposed soft and hard rock etc with all lifts stacking the excavated soil not more then 3 mtr clear from thr edge of the excavation and then returning the stacked soil in	21.00	cum	
2	Providing and laying cement concrete 1:6:12(1cement:6 sand: 12 graded stone aggregate 40 mm nominal size) and curing complete excluding the cost of form work in foundation and plinth within all leads and lifts	9.00	cum	
3	Providing form work with steel plates 3.15 mm thick welded with angle iron frames 30x30x5 mm so as to give fair finish including centering ,shuttering, propping etc. height of propping and centering below supporting floor to ceiling not exceeding 4 meters and removal of the same for-in-situ reinforced concrete and plain concrete work in:-			
	l) Vertical surface such as walls(any thickness) partitions and the like including attached pillasters, butteresses, plinth and string courses and the like.	94.95	Sqm	
4	Providing and laying cement concrete 1:5:10 (1cement :5sand :10 graded stone aggregate 40mm. nominal size) with 15 % plum and curing complete excluding cost of form work in retaining walls/ Breast walls, the size of plums shall usually be 150mm. to 300mm. as per H.P.P.W.D.Specification.	58.50	cum	
5	Providing and fixing gun metal full way valve 80 mm dia for inlet,outlet and scour pipe to filter bed and sedimentation tank with in all leads and lifts and to the entire satisfaction of the Engineer-in-charge.	9.00	Each	
6	Wire crates made of G.I. wire filled with boulders with square and cut faced against the wire (Wire crates to be measured and paid for separately) with in all leads ,lifts, carriage and to the entire satisfaction of engineer in charge.The weight of each boulder should not be less than 18 kgs.	70.32	cum	
7	Wire crates made of G.I. wire filled with boulders with square and cut faced against the wire (boulder fillingsto be measured and paid for separately)with in all leads ,lifts, carriage and to the entire satisfaction of engineer in charge. G.I. wire 5 mm thick corresponding to SWG-8 15cmx15cm mesh.	300.00	sqm	

Terms and conditions:-

Total:-

- 1 The contractor shall be himself responsible for watch and ward the material at site of work.
- 2 The work will be executed as per PWD specifications and to the entire saisfaction of Engineer in charge.
- 3 Final payment shall be made after the successful testing of the work.
- 4 Cement & steel will be issued to the contractor @ Rs. 263/- per bag from IPH store, Shamshi on recoverable basis.
- 5 1% Labour cess will be deducted on gross amount from each bill besides other deductions such as income Tax, Surcharge on Income Tax and Sales Tax etc.
- 6 G.I. wire will be issued from IPH store Shamshi @ 68 /-Kg for which recovery willi be made from each bill .
- 7 The weight of each boulder should not be less than 18 kgs.