

Job No. 1

Schedule of quantity							
Name of Work: - Providing LWSS to NC/PC habitation Ramshehar in Tehsil Nalagarh , Distt. Solan HP. (SH: (SH:- C/O approach road to pump house 2nd stage from RD 0 to 1320) Job No. 1(Under SCSP Demand No. 32)						Estimated Cost :- Rs.	306122.00 /-only
						Earnest Money :- Rs.	6122.00 /-only
						Time : Three months	
Sr. No.	Description of work	No.or Qty.	Unit	Figures	RATE	AMOU	
					Words	NT	
1.00	Cutting in earth work in all classification of earth work such as pick work, jumper work, saturated soil, blasting soft/ hard rock or chiselling soft/ hard rock where blasting is prohibited in all lifts including trimming and dressing of sides levelling of beds to correct grades including shoring, strutting, planking, timbering where ever required, stacking the usable/ serviceable materials/soil separately complete in all respect within all leads and lifts as per the direction of Engineer-in-Charge.	2655.00	cum	Per cum.		#NAME?	
Total in Figures							
Total in Words							

TERMS AND CONDITIONS :-

- 1 The work shall be carried out as per HPPWD/IPH specification and to the entire satisfaction of Engineer -in -Charge.
- 2 Nothing shall be paid for rejected work/material.
- 3 The contractor shall be responsible for watch and word of material at site of work.
- 4 Security, GST, income tax, labour cess and other statutory deduction will be deducted as applicable.

Executive Engineer,
I&PH Divn., Nalagarh.

Job No. 2

Schedule of quantity							
Name of Work: - Providing LWSS to NC/PC habitation Ramshehar in Tehsil Nalagarh , Distt. Solan HP. (SH: (SH:- C/O approach road to pump house 2nd stage from RD 1320 to 3570) Job No. 11(Under SCSP Demand No. 32)						Estimated Cost :- Rs. 406863.00 /-only	
						Earnest Money :- Rs. 8137.00 /-only	
						Time : Three months	
Sr. No.	Description of work	No.or Qty.	Unit	Unit	RATE	AMOU NT	
					Figures	Words	
1.00	Cutting in earth work in all classification of earth work such as pick work, jumper work, saturated soil, blasting soft/ hard rock or chiselling soft/ hard rock where blasting is prohibited in all lifts including trimming and dressing of sides levelling of beds to correct grades including shoring, strutting, planking, timbering where ever required, stacking the usable/ serviceable materials/soil separately complete in all respect within all leads and lifts as per the direction of Engineer-in-Charge.	2920.05	cum	Per cum.		#NAME?	
2.00	Excavation in earth work and filling in 15 cm. layers in foundation and plinths including ramming, watering and consolidating upto a lead of 20 metres and lift upto a 1.5 metres. (Pick work)	251.40	Cum	Per Cum		#NAME?	
3.00	Providing stack Kharanja on Nalah & curved portion of road property hand packed complete in all respect.	50.40	Cum	Per Cum		#NAME?	
Total in Figures							
Total in Words							

TERMS AND CONDITIONS :-

- 1 The work shall be carried out as per HPPWD/IPH specification and to the entire satisfaction of Engineer -in -Charge.
- 2 Nothing shall be paid for rejected work/material.
- 3 The contractor shall be responsible for watch and word of material at site of work.
- 4 Security, GST, income tax, labour cess and other statutory deduction will be deducted as applicable.

Executive Engineer,
I&PH Divn., Nalagarh.