

SCHEDULE OF QUANTITY

Name of work:- Stock storage (SH:- C/O Chowkidar quarter for divisional store at Jatoli in G.P. Sanhol Tehsil & Distt. Solan HP).

Estimated Cost Rs:- 1,68,426/-

Earnest Money Rs:- 3,500/-

Time Period:- 3 months

| <u>S.N</u> | <u>Description of item</u> | <u>Qty</u> | <u>Rate</u> | <u>Unit</u> | <u>Amount</u> |
|-------------------|---|-------------------|--------------------|--------------------|----------------------|
| 0 | | | | | |
| 1 | Providing wood work in frames of doors,windows,clerestory windows and other frames wrought,framed and fixed in position(a) 2nd class deodar wood.including entire carriage of material upto all leads and lifts. | 0.222 | | Cum | |
| 2 | Providing fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory window including black enamelled iron butt hinges with necessary screws in 2nd class deodar/kail wood 40mm thick including entire carriage of material upto all leads and lifts. | 7.56 | | Sqm | |
| 3 | Providing and laying cement concrete 1:2:4(1cement:2approved sand:4app.graded stone aggregate 20mm nominal size) and curing complete excluding cost of form work & reinforcement for reinforced concrete work in:- | | | | |
| a) | suspended floor,roofs, landing and shelves and their supports balconies,beam,girders bressumers and cantilevers upto floor two level.including entire carriage of material upto all leads and lifts. | 8.9175 | | Cum | |
| b) | Wall (any thickness but not less than 0.1m thickness) attached pillasters,buttresses plinth and string courses etc. from top to foundation level upto floor two level and as per the direction of Engineer-in-charge.including entire carriage ofmaterial upto all leads and lifts. | 0.793 | | Cum | |
| 4 | Providing form work with steel plates 3.15mm thick welded with angle iron in frame 30x30x5mm so as to give a fair finish. Including centring,shuttering strutting and propping etc. with wooden battens and ballies height of propping and centring below supporting floor to ceiling not exceeding 4mtrs and removal of the same for insitu reinforced concrete and plain concrete work in:- | | | | |
| a) | Flat surfaces such as soffits suspended floors roofs, landings and the like floors etc upto 200mm in thickness.and as per the direction of Engineer-in-charge. | 75.48 | | Sqm | |
| b) | Vertical surface such as wall of (any thickness) partition and the like including attached pillaster buttresses plinth and string courses and like and as per the direction of Engineer-in-charge .including entire carriage of material upto all leads and lifts. | 5.52 | | Sqm | |
| 5 | 20mm thick cement plaster in single coat on rough side on brick wall in cement 1:3(1cement :3 sand) including carrige of material up to all leads & lifts. | 110.04 | | Sqm | |
| 6 | Providing tor steel reinforcement for RCC work including bending,winding and placing in position complete upto floor two level.as per the direction of Engineer-in-chief including entire carriage of material upto all leads and lifts. | 771 | | Kg | |

7 White washing with lime on decorated wall surfaces(two coats) to give an even shade including throughly brooming the surface to remove all dirt dust mortar dirt and other foreign matter.including entire carriage of material upto all leads and lifts. 110.04

Sqm

Total Rs.:-

TERMS AND CONDITIONS:-

- 1 The undersigned reserves the right to accept or reject any or all the tenders without assigning any reason thereof.
- 2 The work will be got executed as per IPH/PWD specification.
- 3 Security, GST and other statutory deduction will be deducted from the contractor's bill as applicable.
- 4 Nothing will be paid for sub-standard work/material.
- 5 Work shall be started within 15 days after the date of award and completed in stipulated period.
- 6 The Contractor is responsible to watch and ward the material at site of work.
- 7 The quoted rates should include all taxes and carriage charges etc. and nothing extra will be paid on this account
- 8 Useable material found at site while execution will be stacked properly and the same will be the property of the
- 9 Cement @ 275/-per bag & steel @ 4700/- Per Qtl. will be issued from the IPH Store Solan.

- 10 Empty bag required to be handed over to the deptt otherwise the recovery @ Rs. 5/-per bag will be made.

**Executive Engineer
I&PH Division Solan**