

**SCHEDULE OF QUANTITY**

**Name of work**:- Stock storage (SH:- Protection work at Jatoli store Solan in GP Sanhol Tehsil & Distt. Solan HP).

Estimated Cost Rs:- 3,23,598/-

Earnest Money Rs:- 6,500/-

Time Period:- One

Sr. No.	Description of items.	Qty	Rate		Unit	Amount
			In fig	In words		
1	Excavation in foundation and trenches etc. in earth work in all kinds of soil such as pickwork jumper work blasting soft and hard rock and through conglomerate rock upto all leads and lifts stacking the excavated soil not more than 3mtrs clear from the edge of excavation and then returning the stacked soil in 15cm layers when required into plinths sides of foundations etc. consolidating each deposited layers by ramming and watering and then disposing of all surplus excavated earth in all leads and as directed by the Engineer in-charge. (Pick Work 50% ,Jumper Work 50%)	26.25			P/Cum	
2	Providing and laying cement concrete 1:6:12(1cement:6sand:12graded stone aggregate 40mm nominal size and curing complete excluding cost of centering and shuttering in foundation and plinth including entire carriage of material upto all leads and lifts.	7.35			Cum	
3	Cement concrete flooring 1:2:4(1cement:2sand:4graded stone aggregate 20mm nominal size) laid in one layer finished with a floating coat of neat cement 40mm thick including entire carriage of material upto all leads and lifts. ( flooring in top of R/wall)	26.25			P/Sqm	
4	Random rubble masonry/ polygonal rubble masonry (un coursed/ brought to cources) with hard stone of approved quality in foundation and plinth including levelling up with cement concrete 1:6:12 ( 1 cement:6 sand:12 graded aggregate 20mm nominal size in cement mortar 1:6 (1cement:6 sand) inj retaining walls & as per direction of Engineer-in-charge including entire carriage of material upto all leads & lifts.	82.95			Cum	

**Total Rs.:-**

**TERMS AND CONDITIONS:-**

- 1 The undersigned reserves the right to accept or reject any or all the tenders without assigning any reason thereof .
- 2 The work will be got executed as per IPH/PWD specification.
- 3 Security, GST and other statutory deduction will be deducted from the contractor's bill as applicable.
- 4 Nothing will be paid for sub-standard work/material.
- 5 Work shall be started within 15 days after the date of award and completed in stipulated period.
- 6 Stone aggregate/sand shall be used of approved quarry.
- 7 The quoted rates should include all taxes and carriage charges etc. and nothing extra will be paid on this account.
- 8 Useable material found at site while execution will be stacked properly and the same will be the property of the department.
- 9 Cement @ 275/-per bag & steel @ 4700/- per qtl will be issued from the IPH Store Solan.
- 10 Empty bag required to be handed over to the deptt otherwise the recovery @ Rs. 5/-per bag will be made.

Executive Engineer  
IPH Division Solan