

SCHEDULE OF QUANTITY

NAME OF WORK:- PWSS to dried up sources of G.P.Bari,Tunan & Poshna affected due to RHEP in Nirmand Block, Distt. Kullu (H.P)(SH: Providing, laying, jointing and testing of MSERW pipe of 200mm dia from RD 825 to 1085=260Rmt.).	ESTIMATED COST	496144.00
	EARNEST MONEY	9923.00
	TIME LIMIT:	3 Months

Sr. No	Description of items.	Qty	Unit	Rate	In Words	Amount.
				In Fig.		
1	2	3	4	5	6	7
1	Excavation in foundation, trenches (for pipes & pits) upto all depths in all classification of earth work such as pick work, jumper work, saturated soil including bailing and pumping out water, blasting soft/ hard rock or chieselling soft/hard rock where blasting is prohibited in all lifts including trimming and dressing of sides, leveling of beds to correct grade i/c shoring /strutting , planking, timbering & dewatering wherever required, stacking the useable & unuseable material /soil separately & after laying jointing & testing of pipes, returning the useable soil in trenches in 15 cm layers including consolidating of such deposited layer by ramming & watering & then disposing of all surplus excavated soil /unusable material as directed with in all leads & lifts including restoration unmetalled surfaces to its original condition & including cost of diversion for traffic, night signals, fixing caution boards, crossing over trenches for access to houses, fencing etc. complete in all respects with	84.24	Cum			
2	Providing, Laying and Jointing (by way of circumferential butt welded joints by electrical arc welding) and testing in trenches ISO -3183 to L-245 pipe of following diameters (latest with upto date amendment) steel grade-B having wall thickness as spcified below with with bevelled ends and capable of with standing required test presssure in a random lenght of of 4 to 7 meters, including manufacturing reducers/tapers all shorts pieces, bend etc. as per site requirement made from parent tubes. The laying of pipe will include all operation such as cutting, welding, jointing, fabrication of bends, tees, etc. including lowering and laying in excavated trenches to ensure required level including flushing, cleaning and hydraulic testing complete in all respects to the satisfaction of the Engineer in Charge. The fabricated bends shall have three or four cuts having its radius not less than five times the dia of pipe. The pipe shall be factory galvanised (Zink coating both inside and outside) as per relvant IS	84.24	Cum.			
i)	MSERW pipe 200mm dia thickness 4.00mm	260.00	Rmt.			
TERMS AND CONDITIONS ATTACHED						Total

1	Work will be carried out as per HPIPH/PWD Specifications				
2	The contractor shall be responsible for watch and ward of the scheme and in case of theft contractor has to inform Department immediately to lodge FIR for further action.				
3	Final payment shall be released after successful handing over the scheme to the Engineer-in-charge.				
4	1% Income tax, GST as applicable, 1% Labour Cess and 10% security shall be deducted from each bill of the contractor.				
5	The contractor has to do repair work at his own cost except force majot cases.				
					Executive Engineer,
					I&P.H. Division Anni
					Job-2

SCHEDULE OF QUANTITY

Name of work :- PLWSS to Sub-Villages Nishani Kuikod Togi Garahana in Anni Block Distt Kullu (H.P) (S.H: C/O Brick work in Pump House.)

ESTIMATED COST	138826.00
EARNEST MONEY	2777.00
TIME LIMIT:	2 MONTHS.

Sr. No	Description of items.	Quantity	Unit	Rate		Amount
				In Fig.	In Words	
1	2	3	4	5	6	7
1	1st class brick work using common burnt clay building bricks in super structure above plinth upto floor two level in cement mortar 1:6 (1cement : 6 Sand) including crriage of materials in all leads and lifts complete to the entire satisfaction of Engineer-in-charge.	23.72	Cum			
	Total					
TERMS AND CONDITIONS						
1	The work shall be executed as per HPPWD/IPH specification and to the entire satisfaction of the Engineer-in-charge.					
2	The contractor shall be fully responsible for watch and ward of the material at site of work.					
3	The contractor shall be responsible for any accident caused during the construction of the work and the loss if any will be born the contractor.					
3	Cement shall be issued by the department to the contractor @ 312/- per bag & Tor Steel 4900/ Qtl from Sub-Divisional Store, Anni on proper Indent.					
4	Income Tax, Sale Tax, GST and labour cess shall be deducted from the bill of the contractor as applicable .					
5	Nothing shall be paid for rejected material.					
					Executive Engineer,	
					I&P.H. Division Anni	