

Schedule of quantity							
Name of Work:- Providing LWSS Shillon Nallah to Ghariyana in GP Ghariyana Tehsil sunni Distt. Shimla (HP) (SH:- L/J of G.I pipe line.)					Estimated Amount Rs. 2,11,816/-		
					Earnest Money Rs 4200/-		
					Time:- Six Month		
S.N	Description of items.	Quantity/Unit		Rates.		Amount.	
				In fig.	In Words.		
1	Excavation in foundations, trenches etc. in earth work, lift up to 1.50 mtrs. stacking the excavated soil not more than 3 mtrs. clear from the as of excavation and then returning the excavated soil in 15 cm. layers when required into plinths sides of four	546.75	P/cum				
2	Providing and laying in trenches, GMS Tubes (Light Grade), Tube fittings (earth work in trenches to be measured and paid for separately).						
	20 mm Dia	1050	P/Rmt				
	25 mm Dia	950	P/Rmt				
	32 mm Dia	700	P/Rmt				
3	Prov. and fixing Brass-metal wheel valve with wheel.						
	20 mm Dia	1	Each				
	25 mm Dia	1	Each				
4	Making connection of galvanised steel distribution branch with galvanised mild steel main 20mm to 40mm nominal bore by providing and fixing tee including cutting and threading the pipes complete.	15	Each				
	(Rs.) Only	

TERMS AND CONDITIONS

- 1 Use of vibrator in mendatory for RCC/CC work
- 2 5% payment shall be with held for testing of line & civil structures
- 3 The work will be executed as per PWD/IPH specification and as per the direction of the Engineer-in-Charge.
- 4 The contractor is fully responsible for watch and ward of material as issued to him
- 5 The sale tax, Labour cess & Income tax will be deducted from every bill.
- 6 Pipe will be issued by the Deptt to the contractor from IPH Store Suni free of cost.
- 7 The pipe fitting such as Tee,Bend ,Union etc shall be arranged by the contractor at his own cost.
- 8 GST & other deduction will be deducted as per Govt. norms.

Executive Engineer
Jal Shakti Division Suni