

Job No. 1

SCHEDULE OF QUANTITY

Name of Work:- Provoding LWSS to village Chandpur in Tehsil Nalagarh District Solan (HP). (SH: -Laying, jointing & testing of GMS pipein distribution system)

Estimated Cost :- Rs. 243501.00 /-only
Earnest Money :- Rs. 4870.00 /-only
Time :- Two Months

SCHEDULE OF WORKS

Sr. No.	Description of work	No.or Qty.	Unit	RATES		AMOU NT
				Figures	Words	
1.00	Excavation in drains and channels etc. in all kinds of soil such as pick work, jumper work, blasting, soft and hard rock and through conglomerate rock upto all lelands and lifts stacking the excavated soil not more than 3 meters clear from the edge of excavation and then returning the stacked soil in trenches consolidatig each deposited layers by ramming and watering and then disposing of all surlus excavated material within all leads and lifts and like as directed by the Engineer-in-Charge including jungle clearance.	1380.00	Cum	Per Cum		
2.00	Laying, jointing and testing in trenches galvanised mild steel tube of medium grade complete including providing and fixing tube fitting such as union, tees, socket etc (excluding cost of bends and valves) for the following dia as per direction and to the entire satisfaction of Engineer in-charge.					
	a) 25 mm dia (Light grade)	480.00	Rmt.	Per Rmt		
	b) 32 mm dia (Light grade)	2689.00	Rmt.	Per Rmt		
	c) 40 mm dia (Light grade)	1431.00	Rmt.	Per Rmt		
3.00	Providing and fixing of Kirloskar/ Kilburn/IVC/Fouress/Gled/ Bhel/ Leader/ Bir/ Kartar make conforming to IS- 780 including rubber sheet and nut bolts complete of suitable size cast iron dooble flanged sluice valve of following internal dia.					
	40 mm dia PN-1	2.00	Nos	Each		

Total in Figures

Total in Words

TERMS AND CONDITIONS: -

1. The work will be carried out according to the IPH specifications.
2. The work should be done to the entire satisfaction of the Engineer- in -Charge.
3. Secutity, income tax, labour cess and GSTas admissible will be deducted from the bill of the contractor.
4. In addition to normal security, 2% amount of each bill be withheld for want of testing.
5. Nothing will be paid for rejected work.
6. Although GMS pipes will be issued free of cost from Divisional store Nalagarh, but in case of loss or theft from the custody of contractor the same shall be recovered at double the store issue rates which are as under:-
25 mm dia @ Rs. 108/-, 32 mm dia @ Rs, 137/- and 40 mm dia @ Rs. 170/- only.
7. The contracor is fully responsible for watch and ward of the materials at site of work & nothing shall be paid extra for this purpose.

Executive Engineer,
I&PH Divn., Nalagarh.