

**SCHEDULE OF QUANTITY**

Name of work:- Providing wate facility to Rock Cut Temple Masroor in tehsil Dehra Distt. Kangra (HP)

Estimated cost:-Rs. 306533/-

(Sub-Head:- Drilling of Bore well by ODEX 1 No/Percussion/Calyx/RC portable rigs)165mtr deep.

Earnest money:-Rs. 6130/-

Time limit:- One month

Sr. No.	Description of Items	Qty.	Rate in Rs.		Unit	Amount
			Figures/	Words		
1	Transportation of suitable truck mounted DTH & ODEX/Percussion/Calyx/RC drilling with portable rigs alongwith necessary accessories etc.to the site of work and errection of portable rig including levelling etc. complete in all respect as per decision of the Engineer-in-Charge .	1.00 Job			Each.	
2	Drilling bores of 152mm dia as per IS-2800-1979 using ODEX(Tubex) attachment required drilling in collapsible strata conglomerate boulders,pebbles,gravels silt,clay etc. including cost of attachments consumable stores,bits,water,POL etc. with system of simultaneous lowering of 128mm nominal bore 5.0	165.00 Rmt.			Per Rmt	
3	Supplying and lowering of IS marked 125 mm NB 5.0 mm thick fincut MSERW casing pipes as per IS: 4270-2001 and requirement of ODEX attachment from approved manufacturers complete in all respect as per the direction of the Engineer-in-Charge.	165.00 Rmt.			Per Rmt	
4	Providing and fixing of suitable casing shoe and bit tube as per requirement of ODEX attachment complete in all respect as per the direction of the Engineer-in-Charge.	1.00 No			Each.	
5	Colletion and preservation of soil samples in polythene bag complete in all respect as per direction of Engineer-in-charge.	1.00 No			Each.	
6	Development of tube-well/bore well and yield testing with air compressor through V-notch and disinfection etc.as per IS : 2800-1979 complete in all respect as per direction of Engineer-in-Charge.	1.00 No			Per Hour	

**Total:-**

**TERMS & CONDITIONS.**

- 1 The work shall be executed as per PWD/IPH specifications.
- 2 Security, sale tax & Income tax shall be deducted from the bill as per prevalent rules.
- 3 Nothing shall be paid for rejected work/material.
- 4 Crushed stone aggregate shall be used only.
- 5 Any loss of material shall be borne by the contractor.
- 6 1% cess on account of building and other construction workers as per Act-1996.
- 7 The final payment made to the contractor after completion of work and to the entire satisfaction of Engineer-in-Charge.

**Executive Engineer,  
IPH Division, Dehra.**