

SCHEDULE OF QUANTITY							
Name of Work:- A/R & M/O to various Scheme under I&PH Sub Division Sunni Tehsil Sunni Distt. Shimla.					Estimated Amount Rs. 135730/-		
(Sub Head :-Laying & Jointing of GI Pipe & making connections under section Sunni, Mandri &					Earnest Money Rs 2700/-		
S.No	Description of items.	Quantity.		Rates.		Unit.	Amount.
				In fig.	In Words.		
1.01	Excavation in foundation trenches etc.in earth work upto all depths in all kinds of soil such as pick work,jumper work,blasting and chiselling soft/hard rocks where blasting is prohibited in all leads and lifts including trimming and dressing of side levelling of bed to correct grade and returning the stacked soil in trenches in 15cm.layers by ramming and watering and then disposing of all surplus excavated soil as directed in all leads and lifts and soring strutting/timbering and dewatering where ever required including restoration of un metalled/metalled paved surfaces of its original conditions including caution boards in all respect and to the entire satisfaction of the Engineer-in-Charge.	405.00	Per Cubic Mere.			Per Cubic Mere.	
2	Laying ,jointing and testing in trenches GMS tubes (Light grade) tube fittings such as bends,tees unions etc.as per direction and to the entire satisfaction of the Engineer-in-charge.(Earth work in trenches to be measured and paid for separately)in all leads and lifts.	0.00					
2.01	15mm dia	450	Per R/ Metre.			Per R/ Metre.	
2.02	20mm dia	450	Per R/ Metre.			Per R/ Metre.	
2.03	25mm dia	450	Per R/ Metre.			Per R/ Metre.	
3	P/ F Brass fullway valve with hand wheel of superior quality. 15 mm dia.	36	each			each	
3.01	20 mm dia	36	each			each	
3.02	25mm dia	36	each			each	
4	Making connection of galvanised steel distribution branches with galvanised mild steel main 20 mm to 40 mm nominal bore by providing & fixing tee including cutting and threading the pipe complete.	108	each			each	
						<b>Total:-</b>	

**TERMS AND CONDITIONS**

- 5% payment shall be with held for testing of line & civil structures
- The work will be executed as per PWD/IPH specification and as per the direction of the Engineer-in-Charge.
- The contractor is fully responsible for watch and ward of material as issued to him
- Pipe will be issued by the Deptt to the contractor from IPH Store Suni free of cost.
- The pipe fitting such as Tee,Bend ,Union etc shall be arranged by the contractor at his own cost.
- The sale tax, Labour cess & Income tax will be deducted from every bill.

Executive Engineer,  
I&PH Division,Suni,  
Distt Shimla H.P.