

SCHEDULE OF QUANTITY

JOB No.1

T/S by this office vide letter No. IPH-JD-DB-WSS-S/Nagar/2019-20- 4633-34 dated 16.10.2019 for Rs. 13,47,200/- Only.

Name of work :- Remodelling of GWSS H/Basti Dehrot (Indraban) in G.P Nakrari Tehsil Jubbal Distt. Shimla (H.P) (2019-306-1044). (Sub Head: Providing, laying and jointing of GMS tube light class of 15mm = 1060 Rmt., 20mm = 650 Rmt., 25mm = 800 Rmt., 32 mm = 200 Rmt.) (Nodes: 4 to 5, 5 to 6, 6 to 7, 7 to 8, 8 to 9, 5 to 16, 16

Estimated Cost :- 196310.00
Earnest Money Rs:- 4000.00
Time :- 3 Months.

Sr. No.	Sub Head & Item of work.	Quantity	Units.	Rate		Unit	Amount
				In figure	In words		
1.00	Excavation in foundations , trenches etc., in earth work , lift up to 1.50 metres. Stacking the eacavated soil not more than 3 metres clear from the edge of the excavation and then returning the stacked soil in 15 cm. (fifteen centimetres) layers , when required in to plinth and sides of foundations etc., conslolidating each of the dispoisted layer by ramming and watering and then disposing off all excavated soil as directed with in the load of 20 mtrs. Pick and Jumper work etc. complete as per the direction of the Engineer - in - Charge.	575.88 Cum.				Per Cum.	
2.00	Laying and jointing of G.M.S tubes (Light Class) in trenches including refilling & testing etc. complete (earth work to be measured and pais separately)						
2.01	15 mm dia.	1060.00 Rmt.				Per Rmt.	
2.02	20 mm dia.	650.00 Rmt.				Per Rmt.	
2.03	25 mm dia.	800.00 Rmt.				Per Rmt.	
2.04	32 mm dia.	200.00 Rmt.				Per Rmt.	
3.00	Providing and fixing fullway valve of superior quality of various dia. In pipes@ 1 No. in each branch.						
3.01	15 mm dia.	1.00 Nos.				Each.	
2.02	20 mm dia.	1.00 Nos.				Each.	
3.03	25 mm dia.	1.00 Nos.				Each.	
Total :-							

Terms and Conditions.

- 1 *Abrupt changes in gradient and alignment to suit the convenience to contractor shall not be entertained.*
- 2 *The contractor shall be responsible for any loss /damage /theft of materials while in his custody.*
- 3 *The final bill shall be made to the contractor only after storage tank is properly tested for any leakage as per order of the Engineer In charge.*
- 4 *The contractor must see the site of work and study the specification conditions carefully before tendering, the work*
- 5 *GST will be deduct from the bill of Contractor.*
- 6 *The work shall be carried out in accordance with the HPPWD specification. The decision of the Engineer In charge shall be final and binding to the contractor*
- 7 *1% labour cess shall be deducted from the bill*
- 8 *Income tax and sale tax shall be deducted as per prevailing rates.*

Executive Engineer,
I&PH Division,Jubbal.

SCHEDULE OF QUANTITY

JOB No.2

T/S by this office vide letter No. IPH-JD-DB-WSS-S/Nagar/2019-20- 4633-34 dated 16.10.2019 for Rs. 13,47,200/- Only.

Name of work :- Remodelling of GWSS H/Basti Dehrot (Indraban) in G.P Nakrari Tehsil Jubbal Distt. Shimla (H.P) (2019-306-1044). (Sub Head: Providing, laying and jointing of GMS tube light class of 15mm = 1420 Rmt., 20mm = 350 Rmt., 32 mm = 550 Rmt & 40 mm = 250 Rmt.) (Nodes: 1 to 2, 2 to 3, 3 to 4, 2 to 26, 26 to 30, 26 to

Estimated Cost :- 185288.00
Earnest Money Rs:- 3700.00
Time :- 3 Months.

Sr. No.	Sub Head & Item of work.	Quantity	Units.	Rate	In words	Unit	Amount	
				In figure				
1.00	Excavation in foundations , trenches etc., in earth work , lift up to 1.50 metres. Stacking the eacavated soil not more than 3 metres clear from the edge of the excavation and then returning the stacked soil in 15 cm. (fifteen centimetres) layers , when required in to plinth and sides of foundations etc., consolidating each of the dispoited layer by ramming and watering and then disposing off all excavated soil as directed with in the load of 20 mtrs. Pick and Jumper work etc. complete as per the direction of the Engineer - in - Charge.	546.13 Cum.				Per Cum.		
2.00	Laying and jointing of G.M.S tubes (Light Class) in trenches including refilling & testing etc. complete (earth work to be measured and pais separately)							
2.01	15 mm dia.	1420.00 Rmt.				Per Rmt.		
2.02	20 mm dia.	350.00 Rmt.				Per Rmt.		
2.04	32 mm dia.	550.00 Rmt.				Per Rmt.		
2.05	40 mm dia.	250.00 Rmt.				Per Rmt.		
3.00	Providing and fixing fullway valve of superior quality of various dia. In pipes@ 1 No. in each branch.							
2.02	20 mm dia.	1.00 Nos.				Each.		
Total :-								

Terms and Conditions.

- 1 *Abrupt changes in gradient and alignment to suit the convenience to contractor shall not be entertained.*
- 2 *The contractor shall be responsible for any loss /damage /theft of materials while in his custody.*
- 3 *The final bill shall be made to the contractor only after storage tank is properly tested for any leakage as per order of the Engineer In charge.*
- 4 *The contractor must see the site of work and study the specification conditions carefully before tendering, the work*
- 5 *GST will be deduct from the bill of Contractor.*
- 6 *The work shall be carried out in accordance with the HPPWD specification. The decision of the Engineer In charge shall be final and binding to the contractor*
- 7 *1% labour cess shall be deducted from the bill*
- 8 *Income tax and sale tax shall be deducted as per prevailing rates.*

Executive Engineer,
I&PH Division,Jubbal.