

**SCHEDULE OF QUANTITY**

Name of Work:- Providing WSS to PC habitation Dharampur area Tehsil Kasauli Distt. Solan.(SH:- Laying and jointing of GMS pipe 32 mm dia under JJM. (Job No.2)

Estimated cost:- 437555

Earnest money:- 8750

Time:- Three months

Sr. No.	Description of item	Qty	Rate	Unit	Amount
1	Excavation in drains and channel etc in earth work in all kinds of soil such as kankar, moorum shingles conglomerate saturated soil and decomposed soft and hard rock hard rock including including dressing of sides and beds , disposing of excavated earth with all leads, lifts disposed earth to be levelled and neatly dressed and then returning the stacked soil into foundation and trenches etc. including ramming and consolidating the same wherever required with all leads, lifts and including jungle clearance and as per the direction of Engineer-in-charge.	833		P/Cum	
2	Laying,jointing,testing and commissioning in trenches galvanised mild steel tube of following dia (Light grade) including providing and fixing tube fittings such as reducer increasers, sockets, union,tees,bends etc. where ever required and as per the direction of Engineer-in-charge including entire carriage of material upto all leads and lifts.				
	32mm dia	3700		P/Rmt	
3	Providing and fixing gun metal full way valve of following dia as per direction of Engineer-in-charge including entire carriage of material upto all leads and lifts 32mm dia.	1		Each	

**Total:-**

**TERMS AND CONDITIONS:-**

- 1 The undersigned reserves the right to accept or reject any or all the tenders without assigning any reason thereof.
- 2 The work will be got executed as per IPH/PWD specification.
- 3 GST security will be deducted from the contractor bill as applicable.
- 4 Nothing will be paid for sub-standard work/material.
- 5 Work shall be started within 15 days after the date of award and completed in stipulated period.
- 6 Contractor shall be responsible for all leakage in the jointing of pipes, which shall be set right by the contractor at his own cost
- 7 The Contractor is responsible to watch & ward the material at site of work.
- 8 The material/ repair will be guaranteed for a period of one year.
- 9 G.I. pipes will be issued to the contractor free of cost on proper indent at IPH Store Solan. Further carriage and watch and ward will be the responsibility of the contractor. Shortage of G.I. pipe will be recovered on double rate as per Store issue rate.

**Executive Engineer  
J. S. Division Solan**