

SCHEDULE OF QUANTITY						
Name of Work:	Name of work :-Providing and fixing of water bulk meter /flow meter, sluice valves in WSS Kullu Town under AMRUT)	Estimated Cost	₹ 705,757.00			
		Earnest Money	₹ 14,120.00			
		Time Limit :-	3 Months			
SI. No.	Description of work	No.or Qty.	Unit	RATES		AMOUNT
				Figures	Words	Rs. P
1	Providing & fixing Cast Iron Sluice valve (with Rising spindle)as per relevant IS-Specification & dia specified below (with a reputed make like ;Leader,kirloskar,Bir etc. complete in all respect and with entire Satisfaction of engineer Incharge.					
1.01	50 mm nominal dia	2	Each			
1.02	65 mm nominal dia	2	Each			
1.03	100 mm nominal dia	2	Each			
1.04	150 mm nominal dia	6	Each			
1.05	200 mm nominal dia	1	Each			
1.06	250 mm nominal dia	2	Each			
2	Providing and fixing of Full Bore woltmann type ,EEC/MID approved , ISO4064 ,class-B,AMR compatible & IP68 (meter with strainer) reputed make such as Krohne/ Marshall/ Siemens/ABB/SBEM/George Fishers/E &H/ITRON Make at including all fittings as required at site complete in all respect in accordance to relevant BIS and specification with in all lead and lift as per entire satisfaction of Engineer in Charge.					
2.01	200 mm nominal dia	1.00	Each			
3	Providing and fixing of Full Bore electro magnetic flow meter with reputed make such as Krohne/Marshall/Siemens/ABB/SBEM/George Fishers/E &H/ITRON Make at including all fittings as required at site complete in all respect in accordance to relevant BIS and specification with in all lead and lift as per entire satisfaction of Engineer in Charge.					
3.01	250 mm nominal dia	2.00	Each			

TERMS AND CONDITIONS:-

- 1 The work shall be done by the contractor as per HP IPH specifications in practice , IS codes and to the satisfaction of the Engineer-in-Charge.
- 2 Security, labour cess ,taxes/ GST as applicable will be deducted from each bill as per latest Govt.amendments.
- 3 Any other materials related for use in work shall be arranged by the contractor himself within his quoted rates.
- 4 Nothing shall be paid for defective/incomplete work/rejected materials.
- 5 No change of specification shall be permissible without permission of Engineer-in-Charge.
- 6 Any damage caused shall be promptly restored by the contractor at his own expenses.
- 7 Nothing extra will be paid beyond the approved rates, if the alignment of pipe is changed due to site condition.
- 8 The work should be completed with in the stipulated period as mentioned.
- 9 The contractor must visit the site of work before quoting the rates for the above work.
- 10 The contractor to be provided labour register of workers and verify from the labour officer before payments being made under (RE and C.S. Act) 1996.
- 11 The contractor shall be responsible for any loss /damage /theft of materials while in his custody.
- 12 The undersigned reserve the right to accept or reject any or all the tender without assigning any reasons thereof.
- 13 The cost of employer provident fund (EPF) & employer state insurance (ESIC) shall be borne by the contractor. Deposit of the same
- 14 Payment shall be made to the contractor only after successful Testing/comissioning of the all the Sluice valves,Water bulk meter's/flow meter's.

**Executive Engineer,
I&P.H.Division No.1, Kullu.**