



JOB NO.2					
* SCHEDULE OF QUANTITY *					
Name of work :-Providing LWSS Rakh Ram Singh in Tehsil Nalagarh Distt. Solan (HP).(SH:- Laying,jointing and testing of GMS pipe in distribution system) to Aakash Nagar.			Estimated cost :-	249262	/-only
			Earnest money :-	4985	/-only
			Time Limit :-	1 (One) month.	
S.No	Description of item.	Quantity.	Rate	Unit	Amount.
1	Excavation in drain and channels etc.in earth work for pipes upto all depths in all classification of earthwork such as pick work, jumper work, saturated soil including bailing or pumping out water, blasting soft/hard rock or chiseling soft/hard rock where blasting is prohibited in all lifts including jungle clearance wherever required, trimming & dressing of sides, levelling of beds to correct grade including shoring/strutting, planking , timbering & dewatering wherever required stacking the useable/unuseable material/soil seperately & after laying, jointing & testing of pipes, returning the useable soil in trenches in 15cm layers including consolidating of such deposited layer by ramming & watering & then disposing of all surplus excavated soil/ unuseable material as directed with in all leads & lifts including restoration of un-metalled surfaces to its original condition & including cost of diversion for traffic, right signals, fixing caution boards, crossing over trenches for access to houses, fencing etc. complete in all respect with in all leads and lifts and as per direction of the Engineer-in-charge at site of work.	866.25	Cum	Per Cum.	
2	Laying,jointing and testing in trenches galvanised mild steel tube of following dia and grade confirming to BIS 1239 ( with latest ammendment upto date) as per classification of pipe as specified below. The laying of pipe shall confirm to BIS 5822 (With latest ammendment upto date), all kind of specials such as bends of all degrees to made from parent tube, short pieces, tail pieces all made from parent tube within all leads & lifts. (earth work in trenches to be measured and paid for separately).				
	i) 50mm dia(Light Grade)	1290	Rmt.	Per Rmt.	
	ii) 40mm dia(Light Grade)	360	Rmt.	Per Rmt.	
3	Providing and fixing C.I.Sluice valve(with hand wheel)as per IS:780 class upto 300mm dia(including brass spindle and as per IS.2906 class-II for diameter more than 300mm complete with nuts,bolts,rubber insertion etc). The tail pieces if required shall be measured and paid for seperately of following dia. Bir,Kirloskar,leader make PN-1.6 complete in all respect.				
	i) 50mm dia.	1	No.	Each.	
				Total=Rs.	
<b>TERMS AND CONDITIONS:-</b>					
1	The work will be carried out according to the IPH specifications.				
2	The work should be done to the entire satisfaction of the Engineer-in- Charge.				
3	Security, Income Tax, labour cess and Sale Tax as admissible will be deducted from the bill of the contractor.				
4	Nothing will be paid for rejected work.				
5	GMS pipes will be issued free of cost from Divisional store Nalagarh.However, the store issue rates of issued pipes are as				
6	The cement will be issued to the contractor from IPH store Nalagarh and recovery will be made @ Rs 255/- only per bag & the empty bags of				
7	The contractor is fully responsible for watch and ward of the materials at site of work & nothing shall be paid extra for this purpose.				
				Executive Engineer, IPH Division Nalagarh.	