

SCHEDULE OF QUANTITY								
Name of Work:-Prov. LWSS Suresh Pal in GP Khatnol Tehsil Sunni Distt Shimla (HP)								
(Sub Head :- L/J GI Pipe various dia & various R.D & making connection with chamber Node No.1 to 2 village Ohal(Shiel)					Estimated Cost Rs. 346448 /-			
					Earnest Money Rs 6930/--			
					Time Limit:- 3 Month			
S.No	Description of items.	Quantity.		Rates.		Unit.	Amount.	
				In fig.	In Words.			
1	Excavation in foundation trenches etc.in earth work upto all depths in all kinds of soil such as pick work,jumper work,blasting and chiselling soft/hard rocks where blasting is prohibited in all leads and lifts including trimming and dressing of side levelling of bed to correct grade and returning the stacked soil in trenches in 15cm.layers by ramming and watering and then disposing of all surplus excavated soil as directed in all leads and lifts and soring strutting/timbering and dewatering where ever required including restoration of un metalled/metalled paved surfaces to its original conditions including caution boards in all respect and to the entire satisfaction of the Engineer-in-Charge.	968.99	Cum			Per Cubic metre.		
2	Laying ,jointing and testing in trenches GMS tubes(light duty)tube fittings such as bends ,tees,union etc.as per direction and to the entire satisfaction of the engineer-in-charge.(Earth work in trenches to be measured and paid for separately) in all leads and lifts.							
	15 mm dia	185.00	Rmt			Per running metre		
	20mm dia	3215.00	Rmt			Per running metre		
3	P/ F Brass fullway valve with hand wheel of superior quality.							
	15 mm dia	5.00	Nos			each		
	20mm dia	1.00	Nos			each		
4	Making connection of galvanised steel distribution branches with galvanised mild steel main 15 mm to 40 mm nominal bore by providing & fixing tee including cutting and threading the pipe complete.	6.00	Nos			each		
5	P/ F Brass bib Tap of superior quality ISI mark Heavy Type.							
	15 mm dia	5.00	Nos			each		
6	Providing & Fixing of steel Chamber 600x600x450 mm with locking arrsgments make by 1 mm thick MS Sheet 40x40x5 mm thick Angle welded fitting complete including applying a primering coat of red leas paint with CC 1:2:4 20 mm nominal size..	1.00	Nos			each		
					(Rs. .) Only		Total:-	

TERMS AND CONDITIONS

- 5% payment shall be with held for testing of line & civil structures
- The work will be executed as per PWD/IPH specification and as per the direction of the Engineer-in-Charge.
- The contractor is fully responsible for watch and ward of material as issued to him
- Pipe will be issued by the Deptt to the contractor from IPH Store Suni free of cost.
- The pipe fitting such as Tee,Bend ,Union & steel chamber etc shall be arranged by the contractor at his own cost.
- The sale tax, Labour cess & Income tax will be deducted from every bill.

Executive Engineer,
Jal Shakti Division,Suni,
Distt Shimla H.P.