

DRAFT SCHEDULE OF QUANTITY						
Name of Work: Augmentation & Improvement of WSS to village Kahra to Uttersal Area in G.P. Kamand Tehsil sadar Distt Mandi H.P. (SH:-Laying , Jointing,testing and carriage of G.I. pipes of 25 mm dia from Node "E" to "E7" RD 0 to 1250)					Estimated Cost :- <input type="checkbox"/> 136,715.00	
					Earnest Money :- <input type="checkbox"/> 2,800.00	
					Time Period: Three Months	
Sl. No.	Description of work	No. or Qty.	RATE In		Unit	AMOUNT Rs. P
			Figures	Words		
1	Excavation in foundation and trenches etc. in earth work in all kinds of soil such as pick work, jumper work, blasting soft or hard rock or by chiselling soft or hard rock where blasting is prohibited in all leads and lifts including trimming / dressing of sides and bed, stacking the excavated soil clear from the edge of excavation and returning the excavated soil after completion of work in 15cm layers when required into plinth, sides of foundation etc. consolidating each deposited layers by ramming and watering and then disposing of all surplus excavated soil complete in all respect as per direction and to the entire satisfaction of the Engineer-in-Charge.	335.13 cum			Per cum	
2	Laying jointing and testing in trenches GMS tubes(Light Class) including tube fitting such as bends, tees,air valves unions and collars etc. of following dia as per direction and to the entire satisfaction of the engineer in charge in all leads and lifts.					
2.1	25 mm.dia.	1250 Rmt.			Per Rmt.	
3	Providing and fixing of brass wheel valve (H) of following dia. In all leads and lifts.					
3.1	25 mm.dia.	1 No.			Each	
Total in Figures						
Total in Words						

TERMS AND CONDITIONS:-

- 1 The work shall be executed as per HPPWD / JSV specifications.
- 2 The contractor shall be fully responsible for watch and ward of materials at the site of work and in case of any theft or
- 3 The G.I. pipe shall be issued to the contractor free of cost from JSV Divisional Store Padhar on proper indents/challan
- 4 The work shall be completed with in stipulated period.
- 5 The rates are inclusive of carriage of all materials to the site of work in all leads and lifts.
- 6 All GI fittings including required degree bends will be provided by the contr. at his own cost
- 7 Nothing shall be paid for rejected work / material.
- 8 The hydraulic testing of the lines is to be done by contractor at his risk & cost and network should be 100% leakage
- 9 GST, labour cess, income tax, royalty and other taxes as applicable will be deducted from the bills of contractor/ firm.

**Executive Engineer,
Jal Shakti Division,
Padhar.**

DRAFT SCHEDULE OF QUANTITY						
Name of Work: Augmentation & Improvement of WSS to village Kahra to Uttersal Area in G.P. Kamand Tehsil sadar Distt Mandi H.P. (SH:-Laying , Jointing,testing and carriage of G.I. pipes of 25 mm dia from Node "E" to "F" RD 0 to 1150)				Estimated Cost :- <input type="checkbox"/> 125,798.00		
				Earnest Money :- <input type="checkbox"/> 2,600.00		
				Time Period: Three Months		
Sl. No.	Description of work	No. or Qty.	RATE In		Unit	AMOUNT Rs. P
			Figures	Words		
1	Excavation in foundation and trenches etc. in earth work in all kinds of soil such as pick work, jumper work, blasting soft or hard rock or by chiselling soft or hard rock where blasting is prohibited in all leads and lifts including trimming / dressing of sides and bed, stacking the excavated soil clear from the edge of excavation and returning the excavated soil after completion of work in 15cm layers when required into plinth, sides of foundation etc. consolidating each deposited layers by ramming and watering and then disposing of all surplus excavated soil complete in all respect as per direction and to the entire satisfaction of the Engineer-in-Charge.	308.32 cum			Per cum	
2	Laying jointing and testing in trenches GMS tubes(Light Class) including tube fitting such as bends, tees,air valves unions and collars etc. of following dia as per direction and to the entire satisfaction of the engineer in charge in all leads and lifts.					
2.1	25 mm.dia.	1150 Rmt.			Per Rmt.	
3	Providing and fixing of brass wheel valve (H) of following dia. In all leads and lifts.					
3.1	25 mm.dia.	1 No.			Each	
Total in Figures						
Total in Words						

TERMS AND CONDITIONS:-

- 1 The work shall be executed as per HPPWD / JSV specifications.
- 2 The contractor shall be fully responsible for watch and ward of materials at the site of work and in case of any theft or
- 3 The G.I. pipe shall be issued to the contractor free of cost from JSV Divisional Store Padhar on proper indents/challan
- 4 The work shall be completed with in stipulated period.
- 5 The rates are inclusive of carriage of all materials to the site of work in all leads and lifts.
- 6 All GI fittings including required degree bends will be provided by the contr. at his own cost
- 7 Nothing shall be paid for rejected work / material.
- 8 The hydraulic testing of the lines is to be done by contractor at his risk & cost and network should be 100% leakage
- 9 GST, labour cess, income tax, royalty and other taxes as applicable will be deducted from the bills of contractor/ firm.

**Executive Engineer,
Jal Shakti Division,
Padhar.**

DRAFT SCHEDULE OF QUANTITY						
Name of Work: Augmentation & Improvement of WSS to village Kahra to Uttersal Area in G.P. Kamand Tehsil sadar Distt Mandi H.P. (SH:-Laying , Jointing ,testing and carriage of Gravity Main G.I. pipes of 40mm dia from Node "B" to "E" RD 0 to 4180)				Estimated Cost :- ₹ 494,189.00		
				Earnest Money :- ₹ 9,900.00		
				Time Period: Three Months		
SI. No.	Description of work	No. or Qty.	RATE In Figures		Unit	AMOUNT Rs. P
			Figures	Words		
1	Excavation in foundation and trenches etc. in earth work in all kinds of soil such as pick work, jumper work, blasting soft or hard rock or by chiselling soft or hard rock where blasting is prohibited in all leads and lifts including trimming / dressing of sides and bed, stacking the excavated soil clear from the edge of excavation and returning the excavated soil after completion of work in 15cm layers when required into plinth, sides of foundation etc. consolidating each deposited layers by ramming and watering and then disposing of all surplus excavated soil complete in all respect as per direction and to the entire satisfaction of the Engineer-in-Charge.	1120.66 cum			Per cum	
2	Laying jointing and testing in trenches GMS tubes(Light Class) including tube fitting such as bends, tees,air valves unions and collars etc. of following dia as per direction and to the entire satisfaction of the engineer in charge in all leads and lifts.					
2.1	40mm.dia.	4180 Rmt.			Per Rmt.	
3	Providing and fixing of brass wheel valve (H) of following dia. In all leads and lifts.					
3.1	40mm.dia.	1 No.			Each	
Total in Figures						
Total in Words						

TERMS AND CONDITIONS:-

- 1 The work shall be executed as per HPPWD / JSV specifications.
- 2 The contractor shall be fully responsible for watch and ward of materials at the site of work and in case of any theft or loss the recovery shall be made at the double cost of store issue rates.
- 3 The G.I. pipe shall be issued to the contractor free of cost from JSV Divisional Store Padhar on proper indents/challan
- 4 The work shall be completed with in stipulated period.
- 5 The rates are inclusive of carriage of all materials to the site of work in all leads and lifts.
- 6 All GI fittings including required degree bends will be provided by the contr. at his own cost
- 7 Nothing shall be paid for rejected work / material.
- 8 The hydraulic testing of the lines is to be done by contractor at his risk & cost and network should be 100% leakage proof and final payment shall be released only there after.
- 9 GST, labour cess, income tax, royalty and other taxes as applicable will be deducted from the bills of contractor/ firm.

**Executive Engineer,
Jal Shakti Division,
Padhar.**

DRAFT SCHEDULE OF QUANTITY						
Name of Work: Augmentation & Improvement of WSS to village Kahra to Uttersal Area in G.P. Kamand Tehsil sadar Distt Mandi H.P. (SH:-Laying , Jointing,testing and carriage of G.I. pipes of 20 mm dia from Node "B" to "D" RD 0 to 3440)				Estimated Cost :- <input type="checkbox"/> 375,796.00		
				Earnest Money :- <input type="checkbox"/> 7,600.00		
				Time Period: Three Months		
Sl. No.	Description of work	No. or Qty.	RATE In		Unit	AMOUNT Rs. P
			Figures	Words		
1	Excavation in foundation and trenches etc. in earth work in all kinds of soil such as pick work, jumper work, blasting soft or hard rock or by chiselling soft or hard rock where blasting is prohibited in all leads and lifts including trimming / dressing of sides and bed, stacking the excavated soil clear from the edge of excavation and returning the excavated soil after completion of work in 15cm layers when required into plinth, sides of foundation etc. consolidating each deposited layers by ramming and watering and then disposing of all surplus excavated soil complete in all respect as per direction and to the entire satisfaction of the Engineer-in-Charge.	922.26 cum			Per cum	
2	Laying jointing and testing in trenches GMS tubes(Light Class) including tube fitting such as bends, tees,air valves unions and collars etc. of following dia as per direction and to the entire satisfaction of the engineer in charge in all leads and lifts.					
2.1	20 mm.dia.	3440 Rmt.			Per Rmt.	
3	Providing and fixing of brass wheel valve (H) of following dia. In all leads and lifts.					
3.1	20 mm.dia.	1 No.			Each	
Total in Figures						
Total in Words						

TERMS AND CONDITIONS:-

- 1 The work shall be executed as per HPPWD / JSV specifications.
- 2 The contractor shall be fully responsible for watch and ward of materials at the site of work and in case of any theft or loss the recovery shall be made at the double cost of store issue rates.
- 3 The G.I. pipe shall be issued to the contractor free of cost from JSV Divisional Store Padhar on proper indents/challan
- 4 The work shall be completed with in stipulated period.
- 5 The rates are inclusive of carriage of all materials to the site of work in all leads and lifts.
- 6 All GI fittings including required degree bends will be provided by the contr. at his own cost
- 7 Nothing shall be paid for rejected work / material.
- 8 The hydraulic testing of the lines is to be done by contractor at his risk & cost and network should be 100% leakage proof and final payment shall be released only there after.
- 9 GST, labour cess, income tax, royalty and other taxes as applicable will be deducted from the bills of contractor/ firm.

**Executive Engineer,
Jal Shakti Division,
Padhar.**

DRAFT SCHEDULE OF QUANTITY						
Name of Work: Augmentation & Improvement of WSS to village Kahra to Uttersal Area in G.P. Kamand Tehsil sadar Distt Mandi H.P. (SH:-Laying , Jointing,testing and carriage of G.I. pipes of 20 mm dia from Node "D" to "G" RD 0 to 2000)				Estimated Cost :- <input type="checkbox"/> 218,591.00		
				Earnest Money :- <input type="checkbox"/> 4,400.00		
				Time Period: Three Months		
Sl. No.	Description of work	No. or Qty.	RATE In Figures		Unit	AMOUNT Rs. P
			Figures	Words		
1	Excavation in foundation and trenches etc. in earth work in all kinds of soil such as pick work, jumper work, blasting soft or hard rock or by chiselling soft or hard rock where blasting is prohibited in all leads and lifts including trimming / dressing of sides and bed, stacking the excavated soil clear from the edge of excavation and returning the excavated soil after completion of work in 15cm layers when required into plinth, sides of foundation etc. consolidating each deposited layers by ramming and watering and then disposing of all surplus excavated soil complete in all respect as per direction and to the entire satisfaction of the Engineer-in-Charge.	536.20 cum			Per cum	
2	Laying jointing and testing in trenches GMS tubes(Light Class) including tube fitting such as bends, tees,air valves unions and collars etc. of following dia as per direction and to the entire satisfaction of the engineer in charge in all leads and lifts.					
2.1	20 mm.dia.	2000 Rmt.			Per Rmt.	
3	Providing and fixing of brass wheel valve (H) of following dia. In all leads and lifts.					
3.1	20 mm.dia.	1 No.			Each	
Total in Figures						
Total in Words						

TERMS AND CONDITIONS:-

- 1 The work shall be executed as per HPPWD / JSV specifications.
- 2 The contractor shall be fully responsible for watch and ward of materials at the site of work and in case of any theft or loss the recovery shall be made at the double cost of store issue rates.
- 3 The G.I. pipe shall be issued to the contractor free of cost from JSV Divisional Store Padhar on proper indents/challan
- 4 The work shall be completed with in stipulated period.
- 5 The rates are inclusive of carriage of all materials to the site of work in all leads and lifts.
- 6 All GI fittings including required degree bends will be provided by the contr. at his own cost
- 7 Nothing shall be paid for rejected work / material.
- 8 The hydraulic testing of the lines is to be done by contractor at his risk & cost and network should be 100% leakage proof and final payment shall be released only there after.
- 9 GST, labour cess, income tax, royalty and other taxes as applicable will be deducted from the bills of contractor/ firm.

**Executive Engineer,
Jal Shakti Division,
Padhar.**

DRAFT SCHEDULE OF QUANTITY						
Name of Work: Augmentation & Improvement of WSS to village Kahra to Uttersal Area in G.P. Kamand Tehsil sadar Distt Mandi H.P. (SH:-Laying , Jointing,testing and carriage of G.I. pipes of 20 mm dia from Node "B" to "H" RD 0 to 2100)				Estimated Cost :- <input type="checkbox"/> 229,508.00		
				Earnest Money :- <input type="checkbox"/> 4,600.00		
				Time Period: Three Months		
Sl. No.	Description of work	No. or Qty.	RATE In Figures		Unit	AMOUNT Rs. P
			Figures	Words		
1	Excavation in foundation and trenches etc. in earth work in all kinds of soil such as pick work, jumper work, blasting soft or hard rock or by chiselling soft or hard rock where blasting is prohibited in all leads and lifts including trimming / dressing of sides and bed, stacking the excavated soil clear from the edge of excavation and returning the excavated soil after completion of work in 15cm layers when required into plinth, sides of foundation etc. consolidating each deposited layers by ramming and watering and then disposing of all surplus excavated soil complete in all respect as per direction and to the entire satisfaction of the Engineer-in-Charge.	563.01 cum			Per cum	
2	Laying jointing and testing in trenches GMS tubes(Light Class) including tube fitting such as bends, tees,air valves unions and collars etc. of following dia as per direction and to the entire satisfaction of the engineer in charge in all leads and lifts.					
2.1	20 mm.dia.	2100 Rmt.			Per Rmt.	
3	Providing and fixing of brass wheel valve (H) of following dia. In all leads and lifts.					
3.1	20 mm.dia.	1 No.			Each	
Total in Figures						
Total in Words						

TERMS AND CONDITIONS:-

- 1 The work shall be executed as per HPPWD / JSV specifications.
- 2 The contractor shall be fully responsible for watch and ward of materials at the site of work and in case of any theft or loss the recovery shall be made at the double cost of store issue rates.
- 3 The G.I. pipe shall be issued to the contractor free of cost from JSV Divisional Store Padhar on proper indents/challan
- 4 The work shall be completed with in stipulated period.
- 5 The rates are inclusive of carriage of all materials to the site of work in all leads and lifts.
- 6 All GI fittings including required degree bends will be provided by the contr. at his own cost
- 7 Nothing shall be paid for rejected work / material.
- 8 The hydraulic testing of the lines is to be done by contractor at his risk & cost and network should be 100% leakage proof and final payment shall be released only there after.
- 9 GST, labour cess, income tax, royalty and other taxes as applicable will be deducted from the bills of contractor/ firm.

**Executive Engineer,
Jal Shakti Division,
Padhar.**

DRAFT SCHEDULE OF QUANTITY						
Name of Work: Augmentation & Improvement of WSS to village Kahra to Uttersal Area in G.P. Kamand Tehsil sadar Distt Mandi H.P. (SH:-Laying , Jointing,testing and carriage of G.I. pipes of 20 mm dia from Node "B" to C" RD 0 to 2210 & Node "C to C3" RD 0 to 270 = 2480 Rmt)				Estimated Cost :- <input type="checkbox"/> 271,243.00		
				Earnest Money :- <input type="checkbox"/> 5,500.00		
				Time Period: Three Months		
Sl. No.	Description of work	No. or Qty.	RATE In		Unit	AMOUNT Rs. P
			Figures	Words		
1	Excavation in foundation and trenches etc. in earth work in all kinds of soil such as pick work, jumper work, blasting soft or hard rock or by chiselling soft or hard rock where blasting is prohibited in all leads and lifts including trimming / dressing of sides and bed, stacking the excavated soil clear from the edge of excavation and returning the excavated soil after completion of work in 15cm layers when required into plinth, sides of foundation etc. consolidating each deposited layers by ramming and watering and then disposing of all surplus excavated soil complete in all respect as per direction and to the entire satisfaction of the Engineer-in-Charge.	664.89 cum			Per cum	
2	Laying jointing and testing in trenches GMS tubes(Light Class) including tube fitting such as bends, tees,air valves unions and collars etc. of following dia as per direction and to the entire satisfaction of the engineer in charge in all leads and lifts.					
2.1	20 mm.dia.	2480 Rmt.			Per Rmt.	
3	Providing and fixing of brass wheel valve (H) of following dia. In all leads and lifts.					
3.1	20 mm.dia.	2 No.			Each	
Total in Figures						
Total in Words						

TERMS AND CONDITIONS:-

- 1 The work shall be executed as per HPPWD / JSV specifications.
- 2 The contractor shall be fully responsible for watch and ward of materials at the site of work and in case of any theft or loss the recovery shall be made at the double cost of store issue rates.
- 3 The G.I. pipe shall be issued to the contractor free of cost from JSV Divisional Store Padhar on proper indents/challan
- 4 The work shall be completed with in stipulated period.
- 5 The rates are inclusive of carriage of all materials to the site of work in all leads and lifts.
- 6 All GI fittings including required degree bends will be provided by the contr. at his own cost
- 7 Nothing shall be paid for rejected work / material.
- 8 The hydraulic testing of the lines is to be done by contractor at his risk & cost and network should be 100% leakage proof and final payment shall be released only there after.
- 9 GST, labour cess, income tax, royalty and other taxes as applicable will be deducted from the bills of contractor/ firm.

**Executive Engineer,
Jal Shakti Division,
Padhar.**