

SCHEDULE OF QUANTITY

**DRAFT.N.I.T amount Rs.150000/-
E/Money Rs. 3000/-
Time: One Month.**

Name of work: A/R&M/O Medium Lift Irrigation Project to Changer Area from Anandpur Hydrel Channel in Tehsil Sh. Naina Devi Ji District Bilaspur (SH:Providing and fixing Cast steel NRV 300mm dia class ASA-300 for pumping machinery Zone-2B).

Sr.No	Description of items.	Qty	Rate	Rate in words.	Unit	Amount
2	Providing and fixing double flanged cast steel Non return valve 300mm dia of class ASA-300 of Leader/ KSB/ Kirloskar make as per BS: 1414/API-600 with upto date amendements including nuts and bolts, fiber seat along with providing and welding of mating flanges on both side with working pressure 52kg/cm2 as per direction of the Engineer-in-charge. Ttoal head: 391.51 mtr	1			Each	
					Total	0

- 1 **The work shall be executed as per IPH / PWD specification and to the entire satisfaction of the Engineer-in-charge.**
- 2 The rates are inclusive of all carriage in all leads and lifts.
- 3 Nothing shall be paid for rejected work / materials.
- 4 10% security, income tax and GST will be deducted from each running bill of the contractor.
- 5 The guarantee of Non Return valve will be for a period of 12 months from date of commissioning.
- 6 1% labour cess charges will be deducted from the contractor bill.
- 7 The contractor should be registered with EPF organisation.

Executive Engineer
I&PH Division Bilaspur