

SCHEDULE OF QUANTITY

Name of Work:- Providing of WSS Kandhi Tikker inGP. Poura Kothi Tehsil Nihri, Distt. Mandi HP. (SH: Laying, jointing & testing of GI. pipes Gravity main Node A-B 50 mm dia 6500 Rmt Phase IInd).	ESTIMATED	757926.00			
	EARNEST	15200.00			
	TIME LIMIT:	3 Month.			
Sr. No.	Items of work	Quantity	Unit	Rate	Amount
1	2	3		4	5

1 Excavation in foundation and trenches etc.(for pipes & pits) in earth work in all kinds of soil such as pick work, jumper work, blasting soft or hard rock or by chiselling soft or hard rock where blasting is prohibited in all leads and lifts including trimming / dressing of sides and bed, stacking the excavated soil clear from the edge of excavation and returning the excavated soil after completion of work in 15cm layers when required into plinth, sides of foundation etc. consolidating each deposited layers by ramming and watering and then disposing of all surplus excavated soil complete in all respect as per direction and to the entire satisfaction of the Engineer-in-Charge.

2340.00 Cum

- 2 Laying, jointing and testing in trenches galvanized mild steel screwed and socketed /flanged pipes of following diameter and class, tube fittings in trenches i/c carriage of pipes from Sub-Divisional Store to site of work,(Earth work in trenches to be measured and paid for separately) complete in all respect and to the entire satisfaction of the Engineer-in-charge: **(LR)**.

a 50 mm dia.

6500.00

TERMS AND CONDITIONS:-

Total

- 1 Work will be carried out as per HP.PWD/IPH Specifications
- 2 GI pipe will be issued to the contractor by the Department free of cost at IPH Divisional Store Karsogwith proper Indent..
- 3 The contractor shall be responsible himself for watch and ward of material at site of work issued to him by the department
- 4 Final payment shall be released after successful testing and entire satisfaction of the Engineer-in-Charge
- 5 1% Income tax ,2% G.S.T. 1% Labour cess and 10 % Scourity will be deducted from each bill of the contractor .
- 6 Nothing shall be paid for rejected work/substandard work.

SCHEDULE OF QUANTITY

Name of Work:- Providing of WSS Kandhi Tikker inGP. Poura Kothi Tehsil Nihri, Distt. Mandi HP. (SH: Laying, jointing & testing of GI. pipes Gravity main Node B-C 40 mm dia 3000 Rmt Phase II nd).				ESTIMATED	325161.00
				EARNEST	6500.00
				TIME LIMIT:	3 Month.
Sr. No.	Items of work	Quantity	Unit	Rate	Amount
1	2	3		4	5

1 Excavation in foundation and trenches etc.(for pipes & pits) in earth work in all kinds of soil such as pick work, jumper work, blasting soft or hard rock or by chiselling soft or hard rock where blasting is prohibited in all leads and lifts including trimming / dressing of sides and bed, stacking the excavated soil clear from the edge of excavation and returning the excavated soil after completion of work in 15cm layers when required into plinth, sides of foundation etc. consolidating each deposited layers by ramming and watering and then disposing of all surplus excavated soil complete in all respect as per direction and to the entire satisfaction of the Engineer-in-Charge.

990.00 Cum

- 2 Laying, jointing and testing in trenches galvanized mild steel screwed and socketed /flanged pipes of following diameter and class, tube fittings in trenches i/c carriage of pipes from Sub-Divisional Store to site of work,(Earth work in trenches to be measured and paid for separately) complete in all respect and to the entire satisfaction of the Engineer-in-charge: **(LR)**.

a 40 mm dia. 3000.00 Rmt

TERMS AND CONDITIONS:-

Total

- 1 Work will be carried out as per HP.PWD/IPH Specifications
- 2 GI pipe will be issued to the contractor by the Department free of cost at IPH Divisional Store Karsogwith proper Indent..
- 3 The contractor shall be responsible himself for watch and ward of material at site of work issued to him by the department
- 4 Final payment shall be released after successful testing and entire satisfaction of the Engineer-in-Charge
- 5 1% Income tax ,2% G.S.T. 1% Labour cess and 10 % Scourity will be deducted from each bill of the contractor .
- 6 Nothing shall be paid for rejected work/substandard work.

SCHEDULE OF QUANTITY

Name of Work:- Providing of WSS Kandhi Tikker inGP. Poura Kothi Tehsil Nihri, Distt. Mandi HP. (SH: Laying, jointing & testing of GI. pipes Gravity main Node K-L 40 mm dia 2000 Rmt Phase I st).				ESTIMATED	216774.00
				EARNEST	4300.00
				TIME LIMIT:	3 Month.
Sr. No.	Items of work	Quantity	Unit	Rate	Amount
1	2	3		4	5

- 1 Excavation in foundation and trenches etc.(for pipes & pits) in earth work in all kinds of soil such as pick work, jumper work, blasting soft or hard rock or by chiselling soft or hard rock where blasting is prohibited in all leads and lifts including trimming / dressing of sides and bed, stacking the excavated soil clear from the edge of excavation and returning the excavated soil after completion of work in 15cm layers when required into plinth, sides of foundation etc. consolidating each deposited layers by ramming and watering and then disposing of all surplus excavated soil complete in all respect as per direction and to the entire satisfaction of the Engineer-in-Charge.
- 660.00 Cum

- 2 Laying, jointing and testing in trenches galvanized mild steel screwed and socketed /flanged pipes of following diameter and class, tube fittings in trenches i/c carriage of pipes from Sub-Divisional Store to site of work,(Earth work in trenches to be measured and paid for separately) complete in all respect and to the entire satisfaction of the Engineer-in-charge: **(LR)**.

a 40 mm dia

2000.00

Rmt

TERMS AND CONDITIONS:-

Total

- 1 Work will be carried out as per HP.PWD/IPH Specifications
- 2 GI pipe will be issued to the contractor by the Department free of cost at IPH Divisional Store Karsogwith proper Indent..
- 3 The contractor shall be responsible himself for watch and ward of material at site of work issued to him by the department
- 4 Final payment shall be released after successful testing and entire satisfaction of the Engineer-in-Charge
- 5 1% Income tax ,2% G.S.T. 1% Labour cess and 10 % Scourity will be deducted from each bill of the contractor .
- 6 Nothing shall be paid for rejected work/substandard work.

Executive Engineer

I&PH Division Karsog