

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages LIS Haripur in G.P Haripur Tehsil & District Solan
(SH:-Protection work to Pump house ,)

Estimated cost Rs. 226085/-

Earnest money Rs. 4520/-

Time: Three months

Sr. No.	Description of item	Qty	Rate		Unit.	Amount
			In fig.	In words.		
1	Excavation in foundation and trenches etc. in earth work in all kinds of soil such as pick work jumper work soft and hard rock and through conglomerate rock upto all leads and lifts stacking the excavated soil not more than 3mtrs clear from the edge of excavation and then returning the stacked soil in 15cm layers when required into plinths sides of foundations etc. consolidating each deposited layers by ramming and watering and then disposing of all surplus excavated earth in all leads and as directed by the Engineer in-charge.	96			P/Cum	
2	Providing and laying cement concrete 1:6:12(1cement:6sand:12graded stone aggregate 40mm nominal size and curing complete excluding cost of centering and shuttering in foundation and plinth including entire carriage of material upto all leads and lifts.	6.75			P/Cum	
3	Providing and laying cement concrete 1:5:10(1cement:5sand:10graded stone aggregate 40mm nominal size) with 15% plum and curing complete excluding cost of form work in walls the size of plums shall usually be 150mm to 300mm as per HPPWD specification. including entire carriage of material upto all leads and lifts.	37.35			P/Cum	
4	Providing form work with steel plates 3.15mm thick welded with angle iron in frame 30x30x5mm so as to give a fair finish. Including centring,shuttering strutting and propping etc. with wooden battens and ballies height of propping and centring below supporting floor to ceiling not exceeding 4mtrs and removal of the same for insitu reinforced concrete and plain concrete work in:-					
a)	Vertical surface such as wall of (any thickness) partition and the like including attached pillaster buttresses plinth and string courses and like and as per the direction of Engineer-in-charge including entire carriage of material upto all leads and lifts.	83.13			P/Sqm	

TERMS AND CONDITIONS:-

- 1 The undersigned reserves the right to accept or reject any or all the tenders without assigning any reason thereof.
- 2 The work will be got executed as per IPH/PWD specification.
- 3 Security, GST and other statutory deductions shall be made as applicable.
- 4 Nothing will be paid for sub-standard work/material.
- 5 Work shall be started within 15 days after the date of award and completed in stipulated period..
- 6 Stone aggregate/sand shall be used of approved quarry.
- 7 Cement @ 275/-per bag will be issued from the IPH Store Solan at Jatoli..
- 8 Empty bag required to be handed over to the deptt otherwise the recovery @ Rs. 5/-per bag will be made.

Total:

Executive Engineer,
IPH Division Solan