

SCHEDULE OF QUANTITY						
Name of work :- Repair and restoration of LWSS Rishta Mishta in anni block Distt Kullu (H.P) (S.H: Repair and maintenance of Pumping Machinery.)				ESTIMATED COST		144463
				EARNEST MONEY		2889
				TIME LIMIT:		2 Months
Sr.No	Description of items.	Quantity	Unit	Rate		Amount.
				In Fig.	In Words	
1	2	3	4	5	6	7
1	Providing and fixing cast steel double flange sluice valve of reputed make such as Bir / Kirloskar/Kartar/Leader make class: - ASA 300, 80mm dia in delivery pipe of pump and capable of withstanding nominal seat pressure as per BIS. As per IS 780 with latest amendments complete in all respect as per direction and to the entire satisfaction of the Engineer-in-Charge	2.00	Nos			
2	Providing and fixing cast steel double flange swing check / non-returning Valve of reputed make such as Bir / Kirloskar/Kartar/Leader make class: - ASA 300, 80mm dia in delivery pipe of pump and capable of withstanding nominal seat pressure as per BIS. As per IS 780 with latest amendments complete in all respect as per direction and to the entire satisfaction of the Engineer-in-Charge	1.00	Nos			
3	Providing and fixing cast steel double flange swing check / non-returning Valve of reputed make such as Bir / Kirloskar/Kartar/Leader make class: - ASA 300, 100mm dia in rising main pipe and capable of withstanding nominal seat pressure as per BIS. As per IS 780 with latest amendments complete in all respect as per direction and to the entire satisfaction of the Engineer-in-Charge	1.00	Nos			
4	Providing and fixing HRC fuse of reputed make such as havels, Kilburn and L&T 200amps cap complete in all respect as per direction and to the entire satisfaction of the Engineer-in-Charge	6.00	Nos			
5	Providing and fixing oil immersed star delta starter of 75 HP capacity of reputed make such as MEI/Kilburn/L&T/ complete including thimbles of suitable capacity with necessary Bolts & Nuts complete in all respect as per direction and to the entire satisfaction of the Engineer-in-Charge	1.00	Nos			
6	Providing and fixing Digital Amp meters of recommended make such as AE/Havels of suitable range with selector switches conforming to BIS 4064-1978 with up-to-date amendments/ relevant code complete in all respect as per direction and to the entire satisfaction of the Engineer-in-Charge	2.00	Nos			
7	Providing and fixing Digital Volta meters of recommended make such as AE/Havels of suitable range with selector switches conforming to BIS 4064-1978 with up-to-date amendments/ relevant code complete in all respect as per direction and to the entire satisfaction of the Engineer-in-Charge	1.00	Nos			
TERMS AND CONDITIONS						
1	The work shall be executed as per HPPWD/IPH specification and to the entire satisfaction of the Engineer-in-charge.					
2	The contractor shall be fully responsible for watch and ward of the material at site of work.					
3	The contractor shall be responsible for any accident caused during the construction of the work and the loss if any will be born the contractor.					
4	Income Tax, Sale Tax, GST and labour cess shall be deducted from the bill of the contractor as applicable .					
5	Nothing shall be paid for rejected material.					

SCHEDULE OF QUANTITY

Name of Work:- Aug. of various WSS under GP Chail, Sarahan, Nore & Rahanoo in Nirmand Block Distt. Kullu HP. (SH: Laying, jointing & testing of GMS pipe 32 mm dia Node No. 4 - 8 from RD 0/2400 to 2400 = 2400 Rmts.)					Estimated Cost:-	227164.00
PHASE - III.					Earnest Money:-	4543.00
					Time:-	3 Months
Sr. No.	Items of work	Qty	Unit	Rate	Amount	
1	2	3	4	5	6	

1	Excavation in foundation and trenches etc.(for pipes & pits) in earth work	594.00	Cum		
2	Laying, jointing and testing in trenches galvanized mild steel screwed and				
2.1	32 mm	2400.00	Rmt		

Terms and conditions

- 1 The work shall be executed as per HPPWD/IPH specifications and to the entire satisfaction of the Engineer-in-charge.
- 2 The GI pipe shall be issued by the department free of cost from IPH Store Anni.
- 3 GI fitting shall be provided by the contractor at their own cost.
- 4 Any loss of by way of theft or mishandling to the pipes issued by the Deptt. Shall be liability of the contractor and the recovery shall be effected from the
- 5 The contractor shall be fully responsible for watch and ward of the material at site of work.
- 6 The contractor shall be responsible for any accident caused during the construction of the work and the loss if any will be born by the contractor.
- 7 Income Tax and labour cess shall be deducted from the bill of the contractor as applicable.

Executive Engineer
I PH Division Anni

SCHEDULE OF QUANTITY

Name of Work:- Aug. of various WSS under GP Chail, Sarahan, Nore & Rahanoo in Nirmand Block Distt. Kullu HP. (SH: Laying, jointing & testing of GMS pipe 15 mm dia Node No. 15 - 18 from RD 5700/0 to 1800 = 1800 Rmts.)				Estimated Cost:-	155577.00
PHASE - III.				Earnest Money:-	3112.00
				Time:-	3 Months
Sr. No.	Items of work	Qty	Unit	Rate	Amount
1	2	3	4	5	6

1	Excavation in foundation and trenches etc.(for pipes & pits) in earth work	445.50	Cum		
2	Laying, jointing and testing in trenches galvanized mild steel screwed and				
2.1	15 mm	1800.00	Rmt.		

Terms and conditions

- 1 The work shall be executed as per HPPWD/IPH specifications and to the entire satisfaction of the Engineer-in-charge.
- 2 The GI pipe shall be issued by the department free of cost from IPH Store Anni.
- 3 GI fitting shall be provided by the contractor at their own cost.
- 4 Any loss of by way of theft or mishandling to the pipes issued by the Deptt. Shall be liability of the contractor and the recovery shall be effected from the contractor.
- 5 The contractor shall be fully responsible for watch and ward of the material at site of work.
- 6 The contractor shall be responsible for any accident caused during the construction of the work and the loss if any will be born by the contractor.
- 7 Income Tax and labour cess shall be deducted from the bill of the contractor as applicable.

Executive Engineer
I&PH Division Anni

SCHEDULE OF QUANTITY

Name of Work:- Aug. of various WSS under GP Chail, Sarahan, Nore & Rahanoo in Nirmand Block Distt. Kullu HP. (SH: Laying, jointing & testing of GMS pipe 20 mm dia Node No. 15 - 16 from RD 5700/0 to 1600 = 1600 Rmts.)				Estimated Cost:-	140186.00
PHASE - III.				Earnest Money:-	2804.00
				Time:-	3 Months
Sr. No.	Items of work	Qty	Unit	Rate	Amount
1	2	3	4	5	6

1	Excavation in foundation and trenches etc.(for pipes & pits) in earth work	396.00	Cum		
2	Laying, jointing and testing in trenches galvanized mild steel screwed and				
2.1	20 mm	1600.00	Rmt.		

Terms and conditions

- 1 The work shall be executed as per HPPWD/IPH specifications and to the entire satisfaction of the Engineer-in-charge.
- 2 The GI pipe shall be issued by the department free of cost from IPH Store Anni.
- 3 GI fitting shall be provided by the contractor at their own cost.
- 4 Any loss of by way of theft or mishandling to the pipes issued by the Deptt. Shall be liability of the contractor and the recovery shall be effected from the
- 5 The contractor shall be fully responsible for watch and ward of the material at site of work.
- 6 The contractor shall be responsible for any accident caused during the construction of the work and the loss if any will be born by the contractor.
- 7 Income Tax and labour cess shall be deducted from the bill of the contractor as applicable.

Executive Engineer
I&PH Division Anni

SCHEDULE OF QUANTITY

Name of Work:- Aug. of various WSS under GP Chail, Sarahan, Nore & Rahanoo in Nirmand Block Distt. Kullu HP. (SH: Laying, jointing & testing of GMS pipe 20 mm dia Node No. 2 - 14 from RD 4500/0 to 500 = 500 Rmts. & 25 mm dia Node No. 2 - 15 from RD 4500 to 5700 = 1200 Rmts.) PHASE - III.				Estimated Cost:-	159335.00
				Earnest Money:-	3187.00
				Time:-	3 Months
Sr. No.	Items of work	Qty	Unit	Rate	Amount
1	2	3	4	5	6
1	Excavation in foundation and trenches etc.(for pipes & pits) in earth work	433.13	Cum		
2	Laying, jointing and testing in trenches galvanized mild steel screwed and	500.00	Rmt.		
2.1	25 mm	1200.00	Rmt.		

Terms and conditions

- 1 The work shall be executed as per HPPWD/IPH specifications and to the entire satisfaction of the Engineer-in-charge.
- 2 The GI pipe shall be issued by the department free of cost from IPH Store Anni.
- 3 GI fitting shall be provided by the contractor at their own cost.
- 4 Any loss of by way of theft or mishandling to the pipes issued by the Deptt. Shall be liability of the contractor and the recovery shall be effected from the contractor.
- 5 The contractor shall be fully responsible for watch and ward of the material at site of work.
- 6 The contractor shall be responsible for any accident caused during the construction of the work and the loss if any will be born by the contractor.
- 7 Income Tax and labour cess shall be deducted from the bill of the contractor as applicable.

Executive Engineer
I&PH Division Anni

SCHEDULE OF QUANTITY

Name of Work:- Aug. of various WSS under GP Chail, Sarahan, Nore & Rahanoo in Nirmand Block Distt. Kullu HP. (SH: Laying, jointing & testing of GMS pipe 25 mm dia Node No. 22 - 23 from RD 1500 to 2750 = 1250 Rmts., 20 mm dia from Node No. 23 - 24 from RD 2750 to 3900 = 1150) PHASE - I.				Estimated Cost:-	217124.00
				Earnest Money:-	4342.00
				Time:-	3 Months
Sr. No.	Items of work	Qty	Unit	Rate	Amount
1	2	3	4	5	6
1	Excavation in foundation and trenches etc.(for pipes & pits) in earth work in all	594.00	Cum		
2	Laying, jointing and testing in trenches galvanized mild steel screwed and	1150.00	Rmt.		
2.1	25 mm	1250.00	Rmt.		

Terms and conditions

- 1 The work shall be executed as per HPPWD/IPH specifications and to the entire satisfaction of the Engineer-in-charge.
- 2 The GI pipe shall be issued by the department free of cost from IPH Store Anni.
- 3 GI fitting shall be provided by the contractor at their own cost.
- 4 Any loss of by way of theft or mishandling to the pipes issued by the Deptt. Shall be liability of the contractor and the recovery shall be effected from the contractor.
- 5 The contractor shall be fully responsible for watch and ward of the material at site of work.
- 6 The contractor shall be responsible for any accident caused during the construction of the work and the loss if any will be born by the contractor.
- 7 Income Tax and labour cess shall be deducted from the bill of the contractor as applicable.

Executive Engineer
I&PH Division Anni