

SCHEDULE OF QUANTITY

**Name of Work:- A/R M/O WSS Sunni Tehsil sunni Distt. Shimla (HP).
(SH:- Replacement of Filter Media).**

Estimated Amount Rs. 490920/-
Earnest Money Rs 9850/-
Time Limit:- 3 Months

S.No	Description of items.	Quantity.		Rates.		Unit.	Amount.
				In fig.	In Words.		
1	Excavation in foundation trenches etc.in earth work lift up to 1.50 mtrs stacking the excavated soil not more than 3 mtrs. cleaf from the as of excavation and then returning the excavated soil in 15 cm. layers when required in to plinths sides of foundations etc consolidating each deposited layer by ramming and watering and then disposing of all surplus excavated soil as directed within a lead of 20 mtrs in replacement of Filter Media .	143.25	Cum			P/Cum	
2	Relaying of Filter Media						
a)	Broken stone screened: clean, washed and graded from 50mm to 75mm from approved source.	15.09	Cum			P/Cum	
b)	Bajari screened : clean washed and graded from 20mm to 25mm from approved source.	15.09	Cum			P/Cum	
3	Providing & Laying						
a)	Course sand screened : clean wahsed and graded from 3mm to 6mm from approved source.	15.09	Cum			P/Cum	
b)	Fine sand screened : clean , washed and graded effective size 0.2 to 0.4 mm with uniformity coefficient 2.0 to 3 from approved source.	82.89	Cum			P/Cum	
c)	Bajari screened : clean , washed and graded from 6mm to 20mm from approved source.	15.09	Cum			P/Cum	
(Rs.) Only.						Total;-	

TERMS AND CONDITIONS

- 1 Use of vibrator is mendatory for RCC/CC work
- 2 5% payment shall be with held for testing of line & civil structures
- 3 The work will be executed as per PWD/IPH specification and as per the direction of the Engineer-in-Charge.
- 4 The contractor is fully responsible for watch and ward of material as issued to him
- 5 The sale tax, Labour cess & Income tax will be deducted from every bill.
- 6 GST & other deduction will be deducted as per Govt. norms.

Executive Engineer
Jal Shakti Division Suni
Distt. Shimla H.P.