

DNIT				Estimated Cost		4,88,587/-
				Earnesdt Money		9772/-
Name Of Work:- Improvement and Extension of LWSS Khatiyar in Tehsil fatehpur Distt Kangra H.P.				Time Limit		3 Month
SH:- Construction of Boundary wall, Gate Pillers, Fixing of Gate and Barbed wire fencing around the store building.						
Sr. No.	Description Of Item	Quantity		Rate	Unit	Amount
1	Excavation in foundation and trenches etc.(in pipes and pits) in all kinds of soils such as pick work, jumper work, blasting in soft/hard rock, chiselling/wedging out of rock/where blasting prohibited) saturated soil stacking the excavated soil as directed by the Engineer-in-charge clear from the edge of excavation and then returning the stacked soil in 15cm layers when required into plinth sides of foundation etc. consolidating each deposited layer by ramming and watering and then disposing of all surplus excavated earth as directed by the Engineer –in-charge.	20.04	cum		per cum	
2	Providing and laying cement concrete 1:6:12 (1Cement:6sand:12 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form work foundation and plinth .	4.30	cum		per cum	
3	Providing form work with steel plates 3.15mm thick welded with angle iron in frame 30x30x5mm, so as to give a fair finish including centring, shuttering , strutting and propping etc. with wooden battens and ballies height of propping and centering below supporting floor to ceiling not exceeding 4meters and removal of the same for insitu reinforced concrete and plain.					
(a)	Proiding form work (Steel Plate) in Foundation, Footing, Bases of column etc and mass concrete.	108.30	Sqm		per sqm	
(b)	Vertical surface such as wall(any thickness) partitions and the like including pillasters,buttresses plinth and string course and the like including entire carriage of materials with in all leads and lifts Providing Tor steel reinforcement for RCC work including bending.	168.00	Sqm		per sqm	
4	Providing and laying cement concrete 1:5:10 (1Cement:5sand:10 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form work foundation and plinth .	28.64	cum		per cum	

5	Brick work using common burnt clay building bricks ( 2nd class in super structure above plinth level up to floor two level in cement mortar 1:6 ( 1 cement : 6 sand )in all leads and lifts.	58.39	cum		per cum	
6	Providing and laying cement concrete 1:3:6 (1Cement:3sand:6 graded stone aggregate 20mm nominal size) and curing complete excluding the cost of form work foundation and plinth .	10.20	cum		per cum	
7	Providing and laying cement concrete work 1:2:4(1cement:2sand: 4 graded stone aggregate 20mm nominal size ) and curing complete excluding the cost of form work and reinforcement for reinforced concrete work in Suspended floors, roofs, landings and shelves and their supports, balconies, beams ,gridders bressumers and cantilevers upto all floor level.	1.09	cum		per cum	
8	15 mm thick cement plaster in single side of brick work in cement mortar 1:6 ( 1 cement : 6 sand )in all leads and lifts complete in all respect as per entire satisfaction of Engineer in charge.	196.25	Sqm		per sqm	
9	Pointing on Brick work with C.M. 1:3 ( 1 cement : 3 sand )in all leads and lifts complete in all respect as per entire satisfaction of Engineer in charge.	196.25	Sqm		per sqm	
10	Providing TOR steel reinforcement for RCC work including bending, binding and placing in position complete upto any floor level	17.42	Kg		Per Kg	
11	Supply and fixing of G.S. Barbed wire fencing complete in all respect as per entire satisfaction of Engineer in charge.	1540.00	Mtr		Per Rmt	
12	Fixing of MS Angles 65x65x6 cmplete in all respect as per entire satisfaction of Engineer in charge.	57.00	Nos		Each	
13	Fixing of Gate made of MS Angles including all fitting materail and welding etc complete in all respect as per entire satisfaction of Engineer in charge.	1.00	Job		L.S.	
14	Finishing wall with water proofing cement paint of approved brand & manufacture & of required shade on undecorated wall surfaces (two coats) to give an even shade after thotoughly brushing the surface to remove all dirt & remains of loose powdered materials.	635.00	Sqm		per sqm	
15	Applying priming coat over new steel and other metal surface after and including preparing the surface by thoroughly cleaning oil, dirt and other foreign matter and coursed with wire brushing fine steel wool scrapers and sand paper complete with ready mixed paint brushing red lead red oxide/Zinc oxide chrome.	13.03	Sqm		per sqm	

16	Painting two coats (Excluding priming coat) on new steel and other metal surface with enamel paint brushing into give an even shade including cleaning the surface of all dirt, dust and other foreign matter enamel paint other than white.	13.03	Sqm		per sqm	
					<b>Total =</b>	<b>0.00</b>

**Term And Conditions**

- 1 WORK SHALL BE DONE AS PER IPH/PWD SPECIFICATIONS.
- 2 NOTHING SHOULD BE PAID FOR REJECTED MATERIAL/ WORK.
- 3 ONLY ISI MARKED MATERIAL WILL BE USED.
- 4 GST WILL BE DEDUCTED AS PER RULES.
- 5 CEMENT SHALL BE DEDUCTED @ 310/- BAG AND STEEL 5160/-QTL ISSUED AGAINST PROPER INDENT AT DIVISIONAL STORE FATEHPUR.
- 6 FINAL PAYMENT SHALL BE RELEASED AFTER COMPLETION OF WORK AT SITE WITH ENTIRE SATISFACTION OF ENGINEER IN CHARGE.

Executive Engineer,  
IPH Division, Fatehpur