

DNIT						
Name of work :- C/O 12 No. Tube Wells in Fatehpur Area in Tehsil Fatehpur Distt. Kangra HP (SH:- C/O Balance work of store building at Fatehpur).					Estimated Cost- 496943/-	
					Earnest Money- 9940/-	
					Time Limit:- 3 Month	
SN	Description of Item	Quantity		Rate	Unit	Amount
1	Steel work welded in built up section, trusses and framed work including cutting, hosing, fixing in position and applying a priming coat of red lead paint in gratings, fraemd guard bar, ladders, railings, brackets and similar work complete in all resepects within all leads and lifts as per direction and complete satisfaction of Engineer in Charge.	3101.88	Kg		P/Kg	
2	Providing and fixing corrugated GI Sheet roofing fixex with galvanised iron J or L hooks bolts and nuts 8 mm diameter with bitmen and GI implet washers filled with white lead cost of Gusset Plate at each Joint complete excluding the cost of purlins rafters and trusses complete in all respects within all leads and lifts as per direction and complete satisfaction of Engineer in Charge.	157.29	Sqm		P/Sqm	
3	Providing Ridges or hips 60 cm over all in plain GI Sheet 0.80 mm thick with galvanised iron J or L hooks bolts and nuts 8 mm dia GI Limpet and bitumen wahsers complete in all respect within all leads and lifts as per direction and complete satisfaction of Engineer in Charge.	16.05	Mtr		P/Mtr	
4	Providing and fixing 15 cm wide 45 cm overall semicircular plain GI sheetgutter 0.80 mm thick with iron brakets 40*3 mm size bolts and nuts and washers etc including making necessary connections with rain water pipe complete as per design within all leads and lifts as per direction and complete satisfaction of Engineer in Charge.	32.10	Mtr		P/Mtr	
5	Conversion of GI sheet to rain water pipe 0.63 mm thick and fixing the same complet in all respect within all leads and lifts as per direction and complete satisfaction of Engineer-in-Charge.					
i	100 mm dia	4.50	Mtr		P/Mtr	
6	Providing and fixing a PGI sheet bend of required degree (0.63 mm thick sheet) for rain water pipe within all leads and lifts as per direction and complete satisfaction of Engineer in Charge.					
i	100 mm dia	2.00	Nos.		Each	
7	Providing wood work in frames of doors, windows and other frames wrought framed and fixed in position using second class deodar wood in all leads and lifts.	0.29	Cum		P/cum	
8	P/F wood penalled glazed or penalled and glazed shutters for doors, windows and clean story window , 40 mm thick i/c black enameled iron with necessary screw with second class deodar wood (40 mm thick) with in all lead and lifts.	8.93	Sqm		P/Sqm	
9	P/F wire gauge shutters using galvanised M.S. wire gauge of I.S. Gauge designation 85 G with wire of dia 0.56 mm for doors, windows and clean story window , including bright finished black enameled iron hinges with necessary screws with second class deodar wood (40 mm thick) with in all lead and lifts.	7.85	Sqm		P/Sqm	
10	Supplying and fixing rolling shutters of approved make made of 80 mm x 1.25mm M.S. laths interlocked together through their entire length and joined together at the end by end locks mountd on specially designed pipe shaft, with brackets side guides and arrangements for inside and outside locking with push pull operation complete but excluding the cost of the top cover and spring with in all lead and lifts.	13.32	Sqm		P/Sqm	
11	Providing and fixing top cover for rolling shutters of approved make made of superior quality material including all material of fitting with in all lead and lifts as per entire satisfaction of Engineer in charge.	3.70	Mtr		Mtr	
12	Providing and fixing rolling shutters operated be bevel gear box and crank handle exceeding 12.00 sq. m. and upto 25.00 sq. m. in area (Average say 18.50 Sq.m.)with in all lead and lifts.	13.32	Sqm		P/Sqm	
13	White washing with lime on undercoated wall surface (Two coats) to give an even shade including thoroughly brooming the surface to remove all dirt dust and other foreign matter.	438.47	Sqm		P/Sqm	
14	Applying priming coat over new wood and wood based surface after and including preparing the surface by thoroughly cleaning oil dirt grease and other foreign matter sand papering and knotting ready mixed paint brushing wood primer pink.	38.16	Sqm		P/Sqm	
15	Painting two coats(excluding priming coat) on new wood and wood based surface with ready mixed paint brushing the give and even shade including cleaning of all dirt dust and other foreign matter and sand papering and stopping with ready mixed paint other than white.	38.16	Sqm		P/Sqm	
16	Wiring for sub main wiring with following sizes of PVC insulated conductor single core cable in surface /recessed PVC conduit as required (2x4 sqmm) of finolex /plaza or some ISI make approved make by HPSEB Department complete in all respects within all leads and lifts as per direction and satisfaction of engineer in charge.	300.00	Rmt		P/Rmt	
17	Providing and installation of 63 Amp Havells/L & T/Anchor make main switch ISI marked complete in all respect as per entire satisfaction of Engineer in charge.	1.00	Nos.		Each	
18	Supplying and fixing of wooden box 50mm deep on surface or in recessed with suitable size pharolic sheets laminated in front including providing and fixing 3 pin 5/6 ampere socket outlet and 5/6 amp. Tumbler / piano type switch connection painting as required (for power plug) complete in all respects within all leads and lifts as per direction and satisfaction of engineer in charge.					
i	200mmx120mm	4.00	Nos.		Each	
ii	120mm x 120mm	2.00	Nos.		Each	
19	Supplying and fixing of 8-way single pole and neutral sheet steel MCB distribution board 240 volts on surface recess complete with copper bushes neutral line earth bar detachable complete inner connection including painting earthing etc. as required complete in all respects as per direction and satisfaction of engineer in charge complete in all respects.	1.00	Nos.		Each	
20	Providing installation and commissioning and testing of of LED bulbs 20 watts fittings including 90 degree GI bend choke reflector of Bajaj /crompton /Greaves make complete in all respects within all leads and lifts as per direction and satisfaction of engineer in charge.	8.00	Nos.		Each	
21	Providing & fixing 3 pin socketoutlet on the existing switch box/cover including connection etc. as required complete in all respects as per direction and satisfaction of engineer in charge complete in all respects.					
i	5/6 Ampere	3.00	Nos.		Each	
ii	15/16 Ampere	2.00	Nos.		Each	

22	Providing fixing testing and comissioning of ceiling fan 1200 mm(category - A) and regulator including wiring of the down rod of standard length (up to 30 cm) with 1.5 sqmm PVC insulated copper conductor single core cable etc. as required complete in all respects as per direction and satisfaction of engineer in charge complete in all respects.	1.00	Nos.		Each	
23	Providing and fixing sliding door door bolts etc of size 250x16 mm complete in all respect as per entire satisfaction of Engineer in charge.	2.00	Nos.		Each	
24	Providing and fixing all tower bolts 200 x 10 mm complete in all respect as per entire satisfaction of Engineer in charge.	4.00	Nos.		Each	
25	Providing and fixing all tower bolts 100 x 10 mm complete in all respect as per entire satisfaction of Engineer in charge.	18.00	Nos.		Each	
26	Providing and fixing all handles 100 mm size complete in all respect as per entire satisfaction of Engineer in charge.	17.00	Nos.		Each	
27	Providing and fixing all hooks 150 mm size complete in all respect as per entire satisfaction of Engineer in charge.	3.00	Nos.		Each	
28	Providing and fixing plain asbestos cement sheet ceiling of approved quality with butt jointing and wood screws complete in all respect as per entire satisfaction of Engineer in charge.(Frame work and cover fillets to be measured and paid for seprately).	59.82	Sqm		P/Sqm	
29	Steel work welded in built up section,trusses and framed work including cutting,hoisting,fixing in position and applying a priming coat of red lead paint in gratings,framed guard bar,ladders,railings,brackets and similar work complete in all respects within all leads and lifts as per direction and complete satisfaction of engineer in charge.	150.48	Kg		P/Kg	
						Total=

Term and Conditions

- 1 Work shall be done as per IPH /PWD specification.
- 2 GST will be deducted as per rules.
- 3 Final payment will be made only after completion of work.
- 4 Nothing shall be paid for rejected Work/Material.
- 5 Material should be ISI marked.

**Executive Engineer
I & PH Division, Fatehpur**