

SCHEDULE OF QUANTITY						Estimated cost :- Rs. 72451/-	
Name of work:- A/R & M/O LWSS Chanoug 2nd stage in Tehsil Suni Distt.Shimla H.P.						Earnest Money:-Rs:-1500/-	
(SH:-Repair of Pump set make KSB WL - 40/16,75 HP . Set No-1)						Time Allowed:- 1Month	
S.No	Description of items.	Quantity.	Rates.		Unit.	Amount	
			In fig.	In Words.			
1	P/F pump shaft EN 9	1	No		Each		
2	P/F Cl Stage ring ,both side Cl. .	32	Nos		Each		
3	P/F Distance bush .	16	Nos		Each		
4	P/F Diffuser rings C I.	16	Nos		Each		
5	P/F Gland Sleeve S.S.	2	Nos		Each		
6	Providing & Fixing impeller GM .	6	Nos		Each		
7	P/F Diffuser Cl. .	6	Nos		Each		
8	P/F Bearing house . C I.	2	Nos		Each		
9	P/F Bearing SKF NU 206 K ECKP.	1	Nos		Each		
10	Providing & Fixing Bearing 7305 .	2	Nos		Each		
11	Providing & Fixing Bearing bracket stud EN-9. .	28	Nos		Each		
12	Providing & Fixing impeller Keys & Coupling Key.	14	Nos		Each		
13	Providing & Fixing Nut & bolt .	3	Kg		/Kg		
14	Providing & Fixing Packing Ring	14	Nos		Each		
15	Providing & Fixing bearing house plate.	2	Nos		Each		
16	Providing & Fixing water seal. .	2	Nos		Each		
17	Providing & Fixing gland plate. .	1	Nos		Each		
18	Providing & Fixing Check nut & Gland Dori.	4	Nos		Each		
19	Providing & Fixing Cooling pipe with nipple long size.	3	Nos		Each		
20	Repair of impeller & defuser & stay wall & Cl welding & turning . .	36	Nos		Each		
21	Carriage of Pump to workshop and back to site & testing complete.	1	Job		/Job		
						Total:-	

TERMS AND CONDITIONS

- 1 The work should be done as per relevant specification and entire satisfaction of Engineer-in-Charge.
- 2 The material shall be supplied / use as per IS specification.
- 3 After repair of Pump / Motor shall give required discharge / satisfaction.
- 4 The work shall be guaranteed for a period of one year.
- 5 Nothing shall be paid for rejected work/ material .
- 6 Prices should be FOR site of work.
- 7 The contractor should have give the credit of dismantled materials or dismantled more shall be handed over to the Department.
- 8 The sale tax & Income tax will be deducted from every bill & 10% security will be deducted.
- 9 The contractor is fully responsible for watch and ward of material as issued to him
- 10 The contractor shall be a own workshop for the same and having sufficient infrastructure .

Executive Engineer
I&PH Division Suni
Distt Shimla H.P.